



PRICE

SEE BELOW

WEBSITE

AS OF JAN 2024

Welded Storage Cabinet - 36 x 24 x 74"



Strength and security for storing your heavy tools and equipment.

- 14-gauge steel with durable powder-coat finish.
- Padlockable handle with three-point locking system.
- Reinforced doors open on full-height hinges.
- Shelves adjust in 2 1/2" increments.

[More Images](#)

MODEL NO.	DESCRIPTION	DIMENSIONS W x D x H	NO. OF SHELVES	SHELF CAPACITY (LBS.)	WT. (LBS.)	PRICE EACH		IN STOCK SHIPS TODAY
						1	2+	
H-4459	Welded Industrial	36 x 24 x 74"	5	1,200	370	\$1,415	\$1,355	1 ADD

SHIPS ASSEMBLED VIA MOTOR FREIGHT

CANTILEVER RACK
24" ARMS
NEW

MH-10

ITEM NAME/NUMBER Starter Straight Cantilever Rack, No. of Sides: 1, 8 Arms, Arm Length: 24" Jarke Product # 3W588 Manufacturer # SC-8J	Web Price ⓘ \$2,089.19 / each
	WEBSITE GRAINGER
	AS OF MARCH 2024

IMAGES



Product Description

Heavy-duty pin-lock cantilever racks hold heavier materials than medium-duty and light-duty cantilever racks, such as heavy bar stock, tube stock, and sheet material. Items can be placed onto or taken off of the racks with a lift truck or forklift. The racks consist of vertical uprights and arms, and they do not require special tools or bolts to assemble. The arms attach to the uprights with a locking pin that holds them securely in place, and the height of the arms can be adjusted on the uprights.

SPECIFICATIONS

Technical Specs			
Item	Cantilever Rack	Overall Width	37"
Number of Sides	1	Overall Depth	32"
Cantilever Arm Style	Straight	Arm Steel Gauge	11
Shelving Type	Starter	Column Steel Gauge	11
Arm Length	24"	Finish	Gray Enamel
Capacity per Arm	2000 lb.	Lip	Removable
Center Brace Length	72"	Lip Height	1-1/2"
Load Capacity	12,530 lb.	Material	Steel
Number of Arms	8	Includes	Arms Adjustable on 3" Centers
Overall Height	8 ft.		

Double Arm Tool Holder



1-800-637-9508

Our Price: \$155.68
AS OF APRIL 2024

IMAGES



Place double arm tool holders at the top or bottom of a pallet rack bay to organize goods that are harder to store such as brooms, rakes, shovels, and tools. With two arms, the divider is equipped to support both short and long-handled items.

Product Details

- Overall Dimensions: 36"d x 5"w x 7"h
- Color: Gray
- Finish: Powder Coat
- Material: Steel
- *Pallet racking not included

- 31"l and 33"l x 1.5"w x 1.5"h arms
- Stores short or long-handled items vertically on pallet racking
- Arms welded at upward angle to stop items from shifting forward
- 2"w clearance between tubing
- Front flat plate for labeling
- Mounts to beam at desired level
- Installs and repositions without tools

Product Code: DIVIDERARM-DBL

PALLET SIGN RACK

3'D X 8'W X 8'H

NEW

HH-4

ITEM NAME/NUMBER

Model #: WB796562N

EXCLUSIVE BRANDS

Global Industrial™ Teardrop Pallet Rack Starter, 96"W X 36"D X 96"H

IMAGES

PRICE

\$559.00



AS OF MARCH 2024



Global Industrial™ TEAR DROP PALLET RACKS Starter Unit
Premium quality pallet racks at a low price. Global Industrial™ pallet racks offer quick and easy, tool free assembly for all your pallet storage needs. These pre-configured starter and add-on industrial storage rack systems are made of durable heavy gauge steel for years of service. Starter Unit includes 2 upright frames and 2 pairs of shelf beams. Heavy duty, one-piece 14 gauge steel uprights allow height adjustments at 2" increments for easy beam adjustment. High strength 15 gauge steel beams have a 1-5/8"H step beam design that accommodates cross bars and decking. Beams provide secure connection to upright frame using a positive 6-way locking action; right to left, front to back and up and down. Lock automatically snaps into place and secures beam. Welded braces provide maximum rigidity and stability. 3-1/4" x 4-1/4" x 12 gauge welded base plate anchors upright to floor and distributes weight evenly. Uprights feature a long lasting epoxy finish. The pallet should overhang the frame by 3" front and back. Interchangeable with Teardrop styles of the following manufacturers: Interlake, Kingway, Steel King, USP, Wireway/Husky, Unarco and Speed Rack. Easy assembly.

27600 lb rated capacity, higher than other pallet racking in the market. Capacity based on 36" beam shelf spacing.

Weights & Dimensions

Width	96 in	Beam Height	4-1/2 in
Depth	36 in	Weight Capacity	27600 lbs
Height	96 in	Column Size	3 x 3 in

Product Details

Assembly Required	Yes	Material	Steel
Beam Ledge Type	Unslotted	Construction Type	Welded Frame
Type	Starter	Description	Global Tear Drop Pallet Rack Add-on
Shelf Capacity	5030 lbs	Manufacturers Part Number	796562N
Color	Orange	Brand	Global Industrial
Number of Levels	2		

PARTS WASHER NEW

MM-8

ITEM NAME/NUMBER



MODEL 16/30

PRICE

WILL NEED TO
CONTACT REP

WEBSITE

www.safety-kleen.com/

AS OF 5-14-2020

IMAGES



SPECIFICATIONS

	Model 16*	Model 30**
Chemistry	Premium Solvent, QSOL 220/300, PD 680 Type II, PRF 680 Type II, Odorless Solvent	Premium Solvent, QSOL 220/300, PD 680 Type II, PRF 680 Type II, Odorless Solvent
Operation Type	Manual	Manual
Floor Space		
Height	53" (134.7 cm)	60" (152.4 cm)
Width	16" (40.7 cm)	19.5" (49.6 cm)
Sink Size		
Height	7.5" (19.1 cm)	8" (20.4 cm)
Width	27.5" (69.9 cm)	33.25" (84.5 cm)
Depth (front to back)	16.25" (41.3 cm)	22.25" (56.6 cm)
Electric Power	115 VAC, 60 Hz, 1.4 A	115 VAC, 60 Hz, 1.4 A
Standard Fill	8 gal. (30.2 L)	Max Fill: 15 gal. (56.8 L)
Operating Temp	Ambient	Ambient
Material	Steel	Steel
Machine Color	Red	Red
Max Workload	25 lbs. (11.3 kg)	25 lbs. (11.3 kg)
Shipping Weight	57 lbs. (25.9 kg)	62 lbs. (28.1 kg)
Max Filled Weight	111 lbs. (50.3 kg)	162 lbs. (73.5 kg)
Listing	cETLus	cETLus

DESCRIPTION

Time tested.

Our legacy sink-on-a-drum has been around more than 50 years. A sink on a 16- or 30-gallon drum parts washer with solvent, featuring a fusible link cover, plastic spigot, hose and brush, and lamp. Soiled parts are manually washed in the sink, with the solvent draining into the reservoir below.

*Certified reconditioned equipment. Local regulations may cause variations in requirements. Drum and chemistry sold separately.

PEDESTAL GRINDER NEW

ITEM NAME/NUMBER JET Benchtop Shop Grinder with Stand 8in. Dia. Wheel Model# JBG-8A/JPS-2A Item# 70607	PRICE \$509.99
	WEBSITE 
	AS OF FEB 2024

IMAGES



SPECIFICATIONS

Item#	70607	Volts	120
Brand	<u>Jet</u>	Spindle Size	5/8
Manufacturer's Warranty	24 months parts / 24 months labor	Cord Length (ft.)	6
Ship Weight	140.0 lbs	Wheel Included	Yes
Wheel Diameter	8	Dimensions L x W x H (in.)	31 x 21 x 19
Speed (RPM)	3,450	Tool Weight	60
Horsepower	1		

COMPUTER CART
NEW

SD-2

ITEM NAME/NUMBER Model #: WB694561BKA Global Industrial™ Mobile Computer Workstation, Black, Assembled	PRICE \$459.95
	WEBSITE globalindustrial.com
	AS OF 12-19-2024

IMAGES



DESCRIPTION	Mobile Computer Workstation from Global Industrial™ is constructed of 20 gauge steel and provides secure storage in the lockable 24-5/8"W x 22-7/8"D x 22-5/8"H lower compartment. CPU shelf adjusts to accommodate either tower or desktop styles. Rear cabinet access holes are provided. Middle 11-1/2"H fixed shelf provides room for printer. The slide out keyboard tray has a comfortable wrist rest area to reduce fatigue, 23"W x 21"D. Rolls easily on 5" polyolefin casters (2 swivel w/brakes, 2 rigid). The top surface is 47-3/4"H for convenient monitor viewing and has 1-1/2"H back and end stops to keep items from rolling off. Wire ties and mounting holes provided for tidy cable management. Durable baked black enamel finish. Cabinet and shelves ship fully assembled.
--------------------	--

IMAGES



Dimensions:


37" L x 27" D x 73" H

Control Panel Dimensions:

25" L x 12" D x 31" H

FESTOON SYSTEM

IMAGES



IMAGES



IMAGES



IMAGES



Dimensions:
90" L x 32" D x 73" H


Control Panel Dimensions:
25" L x 12" D x 31" H



UNDERCARRIAGE WASH ASSEMBLY (WHEEL BLASTERS, GUIDE RAILS, PHOTO EYES, & TRENCHES)

V-7,8,9,10




IMAGES



IMAGES



1,500 GALLON TANK WITH BAFFLE



DESIGN NOTES:

1. CONCRETE 5,000 PSI. @ 28 DAYS
2. HS-20-44 LOADING WITH 12" TO 60" OF COVER
3. REINFORCING ASTM A-615 GRADE 60
4. CONST. JOINT TO HAVE MIN. 1" BUTYL SEALANT

	FLOOR	VERT. FT	FLAT TOP
WEIGHT	4,850 lbs.	2,470 lbs.	6,400 lbs.
VOLUME		375gal.	



SCITUATE RAY PRECAST
120 CLAY PIT ROAD
MARSHFIELD, MA 02050
PHONE # 1-800-440-0009
FAX # 781-837-4320

CONTRACTOR:
WESTON & SAMPSON

JOB NAME:
HOPKINTON DPW

DATE: 6/30/2016

APPROVED BY:

DRAWING BY: JOHN KASPER

SEE ATTACHED PAGE

Cotterman®

VW-11

COTTERMAN ALUMINUM SERIES "A" SAFETY LADDERS

are one-piece set-up assemblies of high strength aluminum alloy. The solid ribbed aluminum steps and platform provide sure footing in areas where dress shoes or high heels are worn. In addition to being lightweight, aluminum ladders are corrosion resistant and easy to clean. They are also non-magnetic.



**LIGHTWEIGHT
ALUMINUM**


FEATURES:

- The structural framework is of 1" O.D. 6061-T6 high strength aluminum alloy tube.
- Both the steps and the top step are 16" or 24" wide and available in solid ribbed extruded aluminum alloy or aluminum grip strut. The steps are 7" deep. The top step is 14" deep.
- All ladders are provided with spring loaded 2" ball bearing swivel brake casters and reinforced rubber tipped legs.
- Ladders are normally furnished with unpainted aluminum mill finish.
- Series A aluminum ladders comply with OSHA 1910.29 and ANSI A14.7 standards with a 350 lb. load rating. Cal-OSHA models also available.


3 STEP
MODEL NO.
A3R2630A3




6 STEP
MODEL NO.
A6R2630A4



A4
SOLID
RIBBED
ALUMINUM
STEPS



A3
HEAVY DUTY
ALUMINUM
GRIP STRUT





WELDED ALUMINUM SAFETY LADDERS

SERIES A

NO. STEPS INCL. TOP STEP	TYPE OF RAILS	TOP STEP HT.	OVER-ALL HT.	18" WIDE AT TOP					26" WIDE AT TOP				
				MODEL NO.	BASE W"xL"	SHPG. WT.	A4 TREAD	A3 TREAD	MODEL NO.	BASE W"xL"	SHPG. WT.	A4 TREAD	A3 TREAD
1	NONE	12"	12"	*A1N1818	18x20	13			*A1N2626	26x20	14		
2	NONE	20"	20"	*A2N1818	20x23	16			*A2N2626	26x23	20		
2	HAND	20"	50"	A2R1818	20x23	19			A2R2626	26x23	21		
3	NONE	30"	30"	A3N1822	22x29	21			A3N2630	30x29	25		
3	HAND	30"	60"	A3R1822	22x29	24			A3R2630	30x29	27		
4	NONE	40"	40"	A4N1822	22x36	26			A4N2630	30x36	30		
4	HAND	40"	70"	A4R1822	22x36	28			A4R2630	30x36	32		
5	HAND	50"	80"	A5R1822	22x43	35			A5R2630	30x43	39		
6	HAND	60"	90"	A6R1824	24x50	39			A6R2630	30x50	44		
7	HAND	70"	100"	-	-	-			A7R2630	30x57	54		
8	HAND	80"	110"	-	-	-			A8R2630	30x63	61		

*Shippable via UPS at additional boxing cost

OPTIONS



COTTERMAN COMPANY IS PROUD TO BE A MEMBER OF THE FOLLOWING ASSOCIATIONS:

MEMBER
ANSI

MHIA
The Material Handling Industry of America
MEMBER COMPANY

MEMBER
SCAFFOLD
INDUSTRY
ASSOCIATION
SIA

National Safety Council

PRICES SUBJECT TO CHANGE WITHOUT NOTICE • TAX NOT INCLUDED • TERMS: NET 30 DAYS • F.O.B. FACTORY
TOLL FREE 800-5- LADDER • 810-679-4400 • FAX 810-679-4510



"CHARGE IT"

MTI
MAINTENANCE
TECHNOLOGY

IMAGES



SECTION VIII

Appendix



westonandsampson.com

55 Walkers Brook Drive, Suite 100
Reading, MA 01867
tel: 978.532.1900

REPORT

May 30, 2025

PREPARED FOR:

Town of Truro

Geotechnical Engineering Report
Department of Public Works Facility
Truro, Massachusetts

WSE Project No. ENG24-1552

May 30, 2025

Town of Truro
c/o Della Rae Donahue
Weston & Sampson Engineers, Inc.
100 Foxborough Blvd, Suite 250
Foxborough, MA 02035

Re: Geotechnical Engineering Report
Proposed Department of Public Works
Truro, Massachusetts

Dear Ms. Donahue:

Weston & Sampson Engineers, Inc. (Weston & Sampson) is pleased to submit our Geotechnical Engineering Report for the referenced project. This report presents descriptions and summaries of our services, encountered subsurface conditions, and geotechnical considerations and recommendations for design and construction of the proposed project.

We appreciate the opportunity to be of service to you. If you have questions concerning this report or require additional information, please contact us at 978-532-1900.

Very truly yours,

WESTON & SAMPSON ENGINEERS, INC.



Stephen T. Spink, PE
Geotechnical Engineering Team Leader

TABLE OF CONTENTS

	Page
1.0 INTRODUCTION	1-1
1.1 Purpose and Scope	1-1
1.2 Existing Site Conditions	1-1
1.2.1 General.....	1-1
1.2.2 Site Topography	1-2
1.2.3 Environmental Site History.....	1-2
1.3 Proposed Conditions	1-2
2.0 SUBSURFACE CONDITIONS	2-1
2.1 Geologic Setting	2-1
2.2 Borings	2-1
2.3 Subsurface Conditions	2-1
2.3.1 General	2-2
2.3.2 Groundwater	2-2
2.4 Geotechnical Laboratory Testing	2-2
3.0 GEOTECHNICAL RECOMMENDATIONS	3-3
3.1 General	3-3
3.2 Existing Non-Engineered Fill	3-3
3.3 Environmental Considerations	3-3
3.4 Shallow Foundations – Main DPW Structure & Salt Shed	3-3
3.5 Slabs On-Grade	3-4
3.6 Canopy Structure Foundations	3-5
3.7 Seismic Design Considerations	3-5
3.8 Retaining Walls	3-6
4.0 CONSTRUCTION CONSIDERATIONS	4-1
4.1 Site Preparation	4-1
4.2 Excavation Considerations.....	4-1
4.3 Subgrade Preparation and Protection.....	4-1
4.4 Fill Materials	4-2
4.5 Slopes.....	4-3
5.0 LIMITATIONS	5-1
5.1 Observation of Construction	5-1
5.2 Variations of Subsurface Conditions and Use of Report	5-1

FIGURES

- Figure 1 Locus Map
Figure 2 Site Plan

APPENDICES

- Appendix A Selected Schematic Design Plans
- Appendix B Boring Logs
- Appendix C Geotechnical Laboratory Test Results
- Appendix D GBA Important Information about this Geotechnical Report

AJC:STS

\\\\wse03.local\\WSE\\Projects\\MA\\Truro MA\\ENG24-1552_Truro Public Works Facility\\07-DesignMaterials\\02-Geotechnical\\Report\\Truro DPW Facility_Geotechnical Engineering Report_05-30-025.docx

1.0 INTRODUCTION

Weston & Sampson Engineers, Inc. (Weston & Sampson) has prepared this geotechnical engineering report for the proposed Truro Department of Public Works (DPW) facility at 17 Town Hall Road in Truro, Massachusetts (hereinafter the “Site”). The Site’s location relative to surrounding physical features is shown in *Figure 1 – Locus Map*.

Our understanding of the existing conditions and the proposed project are based on our recent discussions with the design team and our review of the following information:

- A set of schematic design plans titled “Town of Truro, MA, New Department of Public Works Facility,” prepared by Weston & Sampson and dated May 2, 2025. Selected schematic design plans are included in *Appendix A*.
- A report titled “Immediate Response Action Plan,” prepared by HRP Associates, Inc. (HRP) dated November 4, 2024.
- A presentation titled “Update on DPW and Landfill PFAS Environmental Assessment Activities,” prepared by HRP dated February 26, 2025.

1.1 Purpose and Scope

The purpose of our geotechnical engineering evaluation was to explore subsurface conditions, identify geotechnical considerations, and provide geotechnical engineering recommendations for design and construction of the proposed DPW facility and related site improvements.

Our scope included field reconnaissance, observations of subsurface explorations, geotechnical laboratory testing, geotechnical engineering analyses, and preparation of this report summarizing our geotechnical engineering recommendations.

1.2 Existing Site Conditions

1.2.1 General

The Site is located within a parcel that is owned and operated by the Town of Truro and is generally bordered by Meetinghouse Road to the north, Town Hall Road to the south, and residential properties to the east and west. The existing facility includes three one- to two-story maintenance buildings, a one-story office building, a fuel island with an above-ground fuel tank, material storage areas and sheds, asphalt concrete (AC) paved parking areas and driveways, and associated landscaped areas as shown on *Figure 2 – Site Plan*. Existing subsurface utilities at the Site include water, stormwater drainage, and electric. An existing on-site septic system is also located in the northeastern portion of the Site. Existing site features are shown on the “Existing Conditions Plan” of the above-referenced schematic design plans, which are included in *Appendix A*.

1.2.2 Site Topography

Based on the aforementioned existing conditions plan, grades slope significantly downward from the existing developed portion of the Site to the north, east, and south. Grades in existing developed areas of the Site range from approximately El. 125 to the east to El. 120 to the west. In the undeveloped wooded areas grades decrease from approximately El. 120 to the south to approximately El. 70 to the northeast where the Site is bordered by Meetinghouse Road. Adjacent to the developed portions of the Site, fairly steep slopes of up to about 1H:1V (Horizontal:Vertical) extend to the north and east before transitioning to more gradual slopes of about 4H:1V. Vertical elevations in this report are in feet and reference the North American Vertical Datum of 1988 (NAVD88).

1.2.3 Environmental Site History

Based on the above-referenced report and presentation prepared by HRP regarding environmental assessments completed at the Site, per- and polyfluoroalkyl substances (PFAS) that were above applicable MassDEP standards were detected in groundwater samples collected at the site during a limited site investigation between July and August 2024. Based on the information provided, we understand the PFAS impacts appear to be limited to the northeast corner of the site behind the existing office building. Remedial strategy in conjunction with proposed development at the site is currently planned to include a combination of capping and groundwater treatment.

1.3 Proposed Conditions

Based on the schematic design plans included in *Appendix A*, the existing office and garage buildings are planned to be demolished and replaced with an approximately 23,600 square foot (SF) DPW building, a salt shed, and a canopy. The new DPW building will include offices and employee facilities, vehicle storage and maintenance areas, workshops, and a vehicle wash bay. The finished floor elevation (FFE) of the new DPW building is planned to be El. 124. The existing fuel island is to remain.

Related site improvements are planned to include new underground utilities, a concrete generator pad, AC paved parking areas and driveways, and retaining walls with exposed heights of up to approximately four (4) feet. Cuts and fills on the order of about four (4) feet are anticipated to achieve proposed site grading.

We understand that the new DPW building is planned to be supported using conventional shallow foundations. Structural loads for the new building were not available at the time of this report, but based on our experience with similar structures, we anticipate that loads will be less than 300 kips for columns and 6 kips per lineal foot (klf) for walls. First floor slab-on-grade loads are anticipated to be less than 250 pounds per square foot (psf). We assume that the new building will not include basement and/or below grade areas except for possible below grade vaults in isolated areas.

The recommendations in this report are based on the above stated assumptions. We should be provided with actual project information as it becomes available and have the opportunity to review

and revise our recommendations as necessary if proposed conditions differ from those described above.

2.0 SUBSURFACE CONDITIONS

2.1 Geologic Setting

Surficial geology information available from the Massachusetts Office of Geographic Information (Mass GIS) indicates the site is located in an area of glacial stratified coarse deposits composed predominantly of sand and gravel.

The “Bedrock Geologic Map of Massachusetts” (United States Geological Survey, Zen et. al., 1983) indicates the Site is located within an area of undivided granite, gneiss, and schist of the Proterozoic Z age. Shallow bedrock and outcrops are not mapped in the immediate site vicinity.

2.2 Borings

A total of six test borings (B-1 through B-6) were completed between April 15 and 16, 2025 within the limits of the proposed site improvements as described in Section 1.3. Approximate boring locations are shown in *Figure 2*.

Desmond Well Drilling, Inc. of Orleans, Massachusetts completed the borings using a truck-mounted drill rig to depths of up to approximately 39 feet below the existing ground surface. Standard penetration tests (SPTs) were conducted in each boring by driving a split spoon sampler with an automatic hammer in general accordance with ASTM D1586. Sampling intervals ranged from continuous (every 2 feet) to standard (every 5 feet). Upon completion, each boring was backfilled with drill cuttings. B-3 and B-6 were completed in existing pavement areas and patched at the ground surface with asphalt cold patch.

Weston & Sampson geotechnical engineering representatives observed drilling activities, measured boring locations using a handheld GPS, and prepared logs for each boring. The boring logs are included in *Appendix B*. Select soil samples obtained from the explorations were submitted for geotechnical laboratory testing as described in Section 2.4.

2.3 Subsurface Conditions

Subsurface conditions encountered in the explorations were generally consistent with the mapped surficial geology. Descriptions of the major soil groups encountered in the borings are provided below in order of their general occurrence with depth from ground surface. The general Unified Soil Classification System (USCS) designation for each stratum is included in the descriptions below in parentheses.

Subsurface conditions described below have been interpreted based on a limited number of explorations that were observed by Weston & Sampson. Variations may occur and should be expected between locations. The strata boundaries shown in our boring logs are based on our interpretations and the actual transitions may be gradual. Refer to the boring logs for detailed descriptions of the soil samples collected.

2.3.1 General

Surface Materials – B-3 and B-6 were completed within existing pavement areas and encountered approximately 3 inches of asphalt concrete (AC) pavement. B-4 and B-5 were located in existing landscape areas and encountered approximately 4 inches of topsoil. B-1 and B-2 were advanced in unvegetated areas.

Fill – Existing fill was encountered at the ground surface in B-1 and B-2, and below the surface materials in B-3 through B-6. The fill generally consisted of very loose to medium dense, brown SAND with trace to little non-plastic fines and trace to little gravel (SP, SP-SM, SM). Trace amounts of debris consisting of asphalt, wood, ceramic, glass, and roots were observed within the fill at various locations. The majority of the fill extended to relatively shallow depths of approximately 0.5 to 4 feet except for B-1 where the fill extended to a depth of approximately 13 feet.

Subsoil – Subsoil was encountered below the fill in B-3 through B-5. The subsoil generally consisted of loose, orange SAND with little non-plastic fines, and trace roots (SM). The subsoil extended to depths of approximately 2 to 5 feet.

Native Sand – Native soils encountered below the fill and subsoil in each of the borings generally consisted of loose to medium dense, light brown SAND with trace gravel and trace non-plastic fines (SP). Each boring was terminated within the native soils at depths ranging between approximately 29 and 39 feet.

2.3.2 Groundwater

Groundwater was not encountered in any of the borings completed as part of this geotechnical investigation. Based on the referenced HRP environmental report, groundwater levels at the site were measured at depths between approximately 117 and 122 feet in 2024.

Groundwater levels should be expected to fluctuate with season, variations in precipitation, construction in the area, and other factors. Perched groundwater conditions could exist close to the ground surface or along the top of bedrock surface, especially during and after extended periods of wet weather.

2.4 Geotechnical Laboratory Testing

Selected soil samples obtained during drilling were submitted for particle size analysis (ASTM D6913/D7928) to confirm field classifications. Geotechnical laboratory testing was performed by Thielsch Engineering of Cranston, Rhode Island. The geotechnical laboratory test results are incorporated into our boring logs and included in *Appendix C*.

3.0 GEOTECHNICAL RECOMMENDATIONS

3.1 General

Based on the subsurface conditions encountered in our explorations and our engineering analyses, the primary geotechnical engineering considerations for the proposed project include the presence of existing undocumented (non-engineered) fill and coordination with environmental requirements within portions of the areas of planned development. Geotechnical design and construction recommendations are provided below and in the following sections.

3.2 Existing Non-Engineered Fill

Subsurface conditions encountered in our explorations generally consisted of relatively shallow (i.e., depths of 4 feet or less) non-engineered fill except for B-1 where the fill extended to a depth of up to approximately 13 feet. B-1 was located within the currently developed portion of the Site in relatively close proximity to an existing slope along the northern portion of the Site.

Topsoil, subsoil, and existing non-engineered fill is not suitable (or allowed by the Massachusetts State Building Code, MSBC) for support of foundations or other rigid structural site improvements that could be adversely affected by differential settlement. Topsoil, subsoil, and existing fill should be completely removed from within the zone-of-influence beneath proposed foundations and other structural elements. The 'zone-of-influence' is defined by a plane extending away from the bottom outside edges of footings and other structural site improvements a horizontal distance of two feet in all directions, then down and away at 1H:1V (horizontal:vertical) slopes to the intersection with undisturbed native soils.

The in-place existing fill may provide adequate support of flexible site improvements such as flexible AC pavements provided subgrades are prepared and evaluated as recommended herein.

3.3 Environmental Considerations

As described in the environmental report prepared by HRP, PFAS compounds were detected in the groundwater in some monitoring wells installed at the Site as part of a separate study. Based on the current information, we understand the areas of environmental concern are generally located in the northern/northeastern portions of the Site.

At the time of this report, capping of a portion of the Site in the northeast corner was planned in the general area of the proposed salt shed structure. The design of the cap had not yet been finalized but was anticipated to include a High-Density Polyethylene (HDPE) liner and a layer of soil cover.

As design progresses in this area of the Site, alterations or changes in planned foundation type for the salt shed may be required depending on the impacts of the proposed capping system.

3.4 Shallow Foundations – Main DPW Structure & Salt Shed

Based on the subsurface conditions encountered in our explorations, the proposed DPW facility can be supported using conventional shallow foundations bearing in the native, undisturbed, inorganic,

native sand soils or properly constructed Structural Fill placed directly over such soils following removal of the topsoil, subsoil and existing fill.

A maximum net allowable bearing capacity of 2,000 psf is recommended to be used for design of spread footings. Resistance to lateral loads can be obtained by a passive equivalent fluid pressure of 225 pounds per cubic foot (pcf), ignoring the top 12 inches of embedment, and by a footing base friction coefficient of 0.45. Shallow foundations constructed as recommended herein are anticipated to undergo total and differential settlements of less than 1 inch and ½ inch, respectively.

As noted above, topsoil, subsoil and existing fill are not suitable (or allowed by the Massachusetts Building Code) for support of foundations or other rigid structural site improvements that could be adversely affected by differential settlement. Topsoil, subsoil, existing fill and other unsuitable soils, as determined by the Engineer, should be completely removed from within the zone-of-influence (ZOI) beneath proposed structures and slabs, and the resulting excavation backfilled with compacted Structural Fill.

Foundations for proposed structures should be designed in accordance with the provisions of the current edition of the Massachusetts State Building Code (MSBC). Footings should be embedded at least 4 feet below the nearest proposed adjacent ground surface exposed to freezing.

Existing below grade structures and the existing septic system that may be located within the ZOI of proposed structures should be removed in their entirety and replaced with compacted Structural Fill as described herein.

If footing construction is to occur in wet conditions, the subgrade may be overcut by a few inches, observed by the Engineer for suitability, and then backfilled to the footing subgrade elevation with crushed stone to reduce subgrade disturbance and softening during construction.

If footing construction occurs during freezing conditions, insulating blankets, heaters, or other suitable measures should be employed to prevent foundation subgrades from freezing until the foundations are backfilled sufficiently to prevent frost from reaching the footing subgrades. The Contractor should be responsible for subgrade protection.

3.5 Slabs On-Grade

Slabs on-grade supporting loads up to 250 psf and bearing on properly constructed Structural Fill overlying recompacted, native undisturbed soils are expected to induce less than one inch of total settlement. A minimum of six inches of clean, angular crushed stone with no more than 6 percent passing a #200 sieve is recommended for underslab stone. Any areas contaminated with fines should be removed and replaced with clean stone. If the underslab stone is saturated or trapping water, the water should be removed prior to slab placement.

Based on the subgrade preparation procedures recommended herein and the existing soil conditions, concrete slabs (including mat slab foundations) and pads may be designed using a modulus of subgrade reaction (k_{s1}) of 60 psi/inch. This value for k_{s1} is for a 1 x 1 square foot area, and should be adjusted for larger areas using the following expression:

$$\text{Modulus of Subgrade Reaction } (k_s) = k_{s1} * \left(\frac{B + 1}{2B}\right)^2$$

Where:

k_s = Coefficient of vertical subgrade reaction for loaded area,

k_{s1} = Coefficient of vertical subgrade reaction for a 1 x 1 square foot area, and

B = width of loaded area in feet.

The ground floor slab should be insulated and dampproofed in accordance with the Building Code. Some flooring manufacturers require specific slab moisture levels and/or vapor barriers to validate the warranties on their products. A properly installed and protected vapor flow retardant can reduce slab moisture. If a vapor flow retardant is used, care should be taken not to trap moisture within the overlying granular fill and floor slab concrete.

3.6 Canopy Structure Foundations

As previously described, non-engineered fill was encountered in B-1 to a depth of approximately 13 feet within the northern portion of the Site in the general area of the proposed canopy structure. Due to the depth and density of the existing fill, canopy structures in this area are recommended to be supported using deep foundations consisting of driven piles or helical piers. Due to the size, relatively lightly loaded nature of the proposed structure, cost considerations and potential need to reduce the amount of excavated soils from the Site due to environmental considerations, helical piers are currently anticipated to be the most economical foundation support alternative for the referenced structures.

Helical piers, or other deep foundation alternatives, should fully penetrate the existing fill and loose sand layers to develop their resistance in the underlying soils. The pier design should be stamped by a Professional Engineer licensed in the Commonwealth of Massachusetts and include calculations that demonstrate adequate vertical geotechnical and structural capacities (including resistance to buckling).

Estimated deep foundations depths and capacities will need to be further evaluated as design progresses based on final site layout and structural load requirements.

3.7 Seismic Design Considerations

Seismic site class was determined in accordance with the International Building Code (IBC) as adapted by the Massachusetts State Building Code using a weighted average of SPT blow counts and shear wave velocity data in the upper 100 feet of soil. Based on our explorations within the proposed main building footprint, analyses, and our previous experience with similar geologic conditions, we recommend the project be evaluated using parameters associated with Site Class D.

Liquefaction can occur in loose, saturated, granular soils. Strong shaking, such as that experienced during earthquakes, can cause a sudden loss of shear strength, densification, and subsequent settlement of these soils. Based on the anticipated depth to groundwater in excess of about 100 feet based on measurements at the Site, the soil types and density encountered in our explorations, the risk of structurally damaging ground deformations related to liquefaction is low.

3.8 Retaining Walls

Based on the preliminary design plans, two primary retaining walls are currently planned in the northeast and northwest portions of the site. Both walls are expected to have an exposed wall height of up to about 4 feet or less. Based on the proposed wall heights and subsurface conditions, we recommend the walls be constructed as segmental block retaining walls (SRWs) due to their relatively low construction cost and ability to tolerate differential settlement in areas where undocumented fill is encountered. SRWs generally consist of pre-manufactured stacked masonry blocks placed on a leveling pad of crushed stone.

SRWs should be designed by a Civil Engineer, registered in the Commonwealth of Massachusetts, and hired by the contractor. Design of the retaining wall should include an assessment of sliding, overturning, and internal stability. Based on the maximum proposed wall height of approximately 4 feet, we anticipate that geogrid reinforcement will not be required for the proposed walls, however this should be confirmed by the wall designer. Reinforcement lengths vary but are typically about 70 to 80 percent of the wall height where required.

Retaining Wall Foundations

SRWs can be supported on a minimum 12-inch-thick leveling pad of compacted angular crushed stone overlying either native undisturbed sand or Structural Fill. The crushed stone leveling pad should extend at least 12 inches horizontally past the edges of the bottom blocks, or as recommended by the block manufacturer.

Where encountered at retaining wall foundation subgrade, existing fill should be removed to a minimum depth of 2 feet from within the zone-of-influence (ZOI) below proposed retaining wall leveling pad foundations.

Lateral Pressures

All retaining walls should be designed to resist lateral pressures exerted by soil, water, seismic, temporary construction loads, and any additional surcharge loads including sloped backfill as appropriate.

Lateral earth pressures on retaining walls unrestrained from rotation with level backfill and drainage provided behind the wall should be calculated using an equivalent fluid unit weight of 40 pounds per cubic foot (pcf). This unit weight should be increased to 60 pcf for walls that are restrained from rotation such as embedded building walls or walls connected to structures such as backfilled stem walls supporting floor slabs. For sloping backfill up to 3H:1V, the equivalent fluid unit weights should be increased to 65 pcf for walls unrestrained from rotation and to 95 pcf for walls restrained from rotation.

A minimum uniform lateral pressure of 125 pounds per square foot (psf) should be added to the above pressures and applied over the full backfill height of all walls. The 125 psf lateral pressure is intended to account for vertical surcharge pressures at the tops of walls up to 250 psf. Additional

lateral pressures equal to 0.5 times the additional surcharge pressure should be added to walls where surcharge pressures exceed 250 psf.

We recommend that passive pressures acting on the base of the wall be ignored due to the possibility of future removal of toe material. Driving forces acting on the wall can be resisted by friction along the base of the wall footing using a friction coefficient of 0.45 for SRW blocks bearing on crushed stone and compacted Structural Fill overlying either native undisturbed sand or recompacted existing granular fill at the site.

Backfill and Drainage

All retaining walls should include drainage behind the wall unless designed to resist hydrostatic pressures. A retaining wall drain should consist of a minimum 12-inch wide (horizontal measure) zone of crushed, free-drainage gravel with less than five-percent fines (such as washed crushed stone) with the stone fully encased with a non-woven filter fabric. Weep holes are recommended to assist with drainage of water from behind the wall. We recommend that weep holes be spaced approximately 10 feet on center, or a drainage pipe connected into a surface water drainage system should be installed behind the wall.

Behind the drainage zone, retaining walls should be backfilled with Structural Fill. The SRW designer should provide specific backfill placement and compaction requirements as part of their submitted wall design. Retaining structures typically rotate and displace up to 1 percent of the wall height during development of active pressures behind the wall. We therefore recommend that construction of improvements adjacent to the top of walls be delayed until approximately two weeks after wall construction and backfill.

Stormwater runoff should be collected and diverted away from the retaining wall areas to prevent erosion and to reduce the potential of elevated water pressures developing behind the wall.

4.0 CONSTRUCTION CONSIDERATIONS

4.1 Site Preparation

Prior to earthwork and foundation construction, the areas of proposed development should be prepared by removing any existing structures, foundation elements, and abandoned utilities. Associated pavement, topsoil, subsoil and existing fill materials should also be removed. Excavations resulting from site preparation should be brought back to grade using Structural Fill. Utilities should be removed or properly abandoned using Structural Fill, controlled density fill (CDF), or grouting in such a manner to prevent voids.

4.2 Excavation Considerations

Excavation will be required for site preparation, grading, and construction of foundations and utilities. Surface water should be controlled during construction and prevented from eroding temporary slopes and disturbing excavation and subgrade materials. If excavations encounter perched groundwater, moderate to severe caving should be expected where seepage is present.

All excavations should be made in accordance with applicable OSHA safety regulations. Temporary excavation support may be required depending on depths of excavations and if excavations need to approach the zone-of-influence beneath existing structures, utilities, or other site features. Excavation support systems, if necessary, should be the responsibility of the Contractor and designed by a Professional Engineer licensed in the Commonwealth of Massachusetts. Foundations and utilities should be designed and constructed so that excavations into zones-of-influences below and adjacent to footings are not required.

Based on the groundwater conditions observed during drilling, extensive dewatering is not anticipated to be required during construction. However, depending on excavation depth and the amount of potentially perched groundwater, dewatering may be necessary. Flow rates for dewatering are likely to vary depending on location, soil type, and the season during which the excavation occurs. The dewatering system should be capable of lowering the groundwater table at least 2 feet below the anticipated excavation depths and be kept operational until fill placement and compaction and concrete installation have been completed to at least 2 feet above the groundwater table elevation. The dewatering system should be capable of handling variable flow rates and should be the responsibility of the Contractor.

4.3 Subgrade Preparation and Protection

Based on the subsurface conditions encountered in our explorations, stripping and subgrade preparation will likely expose existing fill, subsoil, and native sand. After stripping (i.e., removal of unsuitable materials), subgrades consisting of native granular soils should be recompacted until dense and stable with several passes of a minimum 12-ton vibratory roller. Weston & Sampson should be contacted to evaluate the exposed subgrade. Subgrades will be evaluated based on probing or observation of a proof roll using a fully loaded 10-wheeled dump truck or suitable alternative.

The native sand is susceptible to disturbance from vehicle and foot traffic. We therefore recommend placement of a minimum of 6 inches of compacted $\frac{3}{4}$ inch crushed stone above the prepared subgrade.

Soft and/or disturbed areas will require over-excavation and backfilling with compacted angular crushed stone or compacted Structural Fill. A geosynthetic separation layer between the excavation subgrade and crushed stone backfill may also be required. We recommend that the project budget and schedule include contingencies for over-excavation and stabilization of soft and variable subgrade conditions.

Soils with more than trace amounts of fines (i.e., silt and clay) are highly susceptible to softening and disturbance by construction activity during wet or freezing weather. Subgrade protection is the responsibility of the contractor, and special precautions and protective measures appropriate for the weather and traffic conditions during construction should be used during earthwork and foundation construction to preserve the integrity of subgrades.

If footing construction occurs during freezing conditions, insulating blankets, heaters, or other suitable measures should be employed to prevent foundation subgrades from freezing until the foundations are backfilled sufficiently to prevent frost from reaching the footing subgrades. The Contractor should be responsible for subgrade protection.

Construction traffic should not operate directly on subgrades. Existing pavement areas can be used as staging areas, but the existing AC pavement section should not be expected to protect subgrades from concentrated heavy construction traffic.

4.4 Fill Materials

Well graded sand and gravel fill with less than approximately 10 percent fines (such as MassDOT M1.03.0-type B Gravel Borrow or M2.01.7 Dense-graded Crushed Stone) is recommended for use as imported Structural Fill in foundation, slab on-grade, and other structural areas. On-site materials meeting the gradation requirements for the aforementioned MassDOT materials may be acceptable for use as Structural Fill if approved by the Geotechnical Engineer. Structural Fill should have a maximum particle size of 3 inches and be placed in maximum 10-inch-thick lifts (measured prior to compaction) with each lift compacted to at least 95 percent of maximum dry density as determined by ASTM D1557 (Modified Proctor) for the specific fill material.

On-site granular soils containing less than approximately 25 percent fines and free of organics, contamination (including metals, VOCs, SVOCs, etc.), and other deleterious materials may be suitable for use as fill in areas outside proposed structures (i.e., Common Fill) if properly moisture conditioned. The native sand encountered in the borings generally appear suitable for re-use as Common Fill provided additional laboratory testing is completed to confirm gradation results prior to the start of fill placement.

In confined areas and where only hand-operated compaction equipment can be used, lift thicknesses should be reduced to not more than 6 inches. In addition to density testing, we

recommend that the fill lifts pass a proof roll using a fully loaded dump 10-wheel truck or equipment of similar size and weight and observed by a geotechnical engineer.

4.5 Slopes

All slopes and excavations should be constructed in accordance with applicable OSHA and local safety standards. Temporary slopes up to 10 feet high can be inclined up to 1.5H:1V provided no seepage or sloughing is present. Equipment should not be allowed to induce vibration or infiltrate water above the slopes and no surcharges should be located within 20 feet of slope crests. Temporary slopes should be expected to ravel somewhat, depending on weather conditions, soil conditions, seepage, and duration of exposure. Soft or loose fill soils and the presence of seepage may require flatter slopes, erosion control measures, drainage elements, and/or temporary excavation support.

Permanent cut and fill slopes up to 10 feet high should be formed at 2H:1V or flatter, however shallower (3H:1V) slopes are recommended for ease of maintenance and mowing. The faces of fill slopes should be overbuilt and cut back into compacted materials with a smooth excavator bucket. If steeper fill slopes are desired, we should be consulted to evaluate the use of grid reinforcement, rock blankets, or rock fill buttresses.

5.0 LIMITATIONS

5.1 Observation of Construction

Satisfactory earthwork and foundation performance depends to a large degree on the quality of construction. Subsurface conditions observed during construction should be compared with those encountered during the subsurface explorations. Recognition of changed conditions often requires experience; therefore, qualified personnel should visit the site with sufficient frequency to detect whether subsurface conditions change significantly from those anticipated. In addition, sufficient monitoring of the contractor's activities is a key part of determining that the work is completed in accordance with the construction drawings and specifications.

5.2 Variations of Subsurface Conditions and Use of Report

We have prepared this report for use by members of the design and construction team for the subject project and this site only. The data and report can be used for estimating purposes, but our report, conclusions, and interpretations should not be construed as a warranty of the subsurface conditions and are not applicable to other sites.

Subsurface explorations indicate soil conditions only at specific locations and only to the depths penetrated. They do not necessarily reflect subsurface conditions that may exist between exploration locations. If subsurface conditions differing from those described are noted during excavation and construction, reevaluation will be necessary.

Site development plans and design details were not finalized at the time this report was prepared. If changes are made in site grades, configuration, design loads, or type of construction for the proposed structures, the conclusions and recommendations may not be applicable. We should be consulted to review final design drawings and specifications to see that our recommendations are suitably followed. If design changes are made, we should be retained to review our conclusions and recommendations and provide a written evaluation or modification. Additional geotechnical engineering analyses and explorations may be necessary.

The recommendations in this report are preliminary as actual subsurface conditions may differ from those interpreted based on our subsurface explorations. In order for our recommendations to be considered final, we must be retained to observe the actual subsurface conditions encountered during construction. Our observations will allow us to interpret the actual conditions present during construction and adapt our recommendations if needed.

Within the limitations of scope, schedule, and budget, our services have been executed in accordance with generally accepted practices in this area at the time this report was prepared. No warranty or other conditions, expressed or implied, is given. For additional information about use of this report, see the Geoprofessional Business Association, Inc (GBA) documents included in *Appendix D*.

FIGURES



SCALE IN FEET






FIGURE 1
LOCUS MAP
TRURO DPW
17 TOWN HALL ROAD
TRURO, MA
BARNSTABLE COUNTY



\\wse03.local\WSE\Projects\MA\Truro MA\ENG24-1552_Truro Public Works Facility\07-DesignMaterials\02-Geotechnical\CAD\Truro DPW - Figure 2 - Site Plan.dwg



Weston & Sampson Engineers, Inc.
55 Walkers Brook Drive, Suite 100
Reading, MA 01867
978.532.1900 800.SAMPSON
www.westonandsampson.com

NOTES

1. THIS PLAN IS BASED ON A GRADING AND DRAINAGE PLAN PREPARED BY WESTON & SAMPSON ENGINEERS, INC. DATED APRIL 15, 2025.
2. APPROXIMATE LIMIT OF PFAS CONTAMINATION AS DETERMINED DURING A LIMITED SITE INVESTIGATION PERFORMED BY HRP ASSOCIATES, INC. BETWEEN JULY AND AUGUST 2024.
3. BORINGS WERE COMPLETED BY DESMOND WELL DRILLING, INC. OF ORLEANS, MA BETWEEN APRIL 15 AND 16, 2025.
4. STORMWATER DESIGN TEST PITS WERE COMPLETED BY TOWN OF TRURO DEPARTMENT OF PUBLIC WORKS PERSONNEL OF TRURO, MA ON APRIL 15, 2025.
5. ALL BORINGS WERE OBSERVED BY A WESTON & SAMPSON ENGINEER.
6. BORING LOCATIONS SHOWN ARE APPROXIMATE AND BASED ON FIELD MEASUREMENTS USING A HANDHELD GPS.

LEGEND


 B-X DESIGNATION AND APPROXIMATE LOCATION OF BORING

GRAPHIC SCALE



SCALE: 1"=60'

ORIENTATION



TITLE

SITE PLAN

PROJECT

TRURO DPW

17 TOWN HALL ROAD
TRURO, MA 02666

FIGURE

FIGURE 2

DATE	04/2025
DRWN BY	AJC
CHKD BY	STS
PRJ. NO.	ENG24-1552
REV. NO.	-

APPENDIX A

Selected Schematic Design Plans

(Refer to Section II for Schematic Design Drawings)

APPENDIX B

Boring Logs

GUIDE TO SUBSURFACE EXPLORATION LOGS



INDEX SHEET 1 GENERAL INFORMATION

GENERAL NOTES AND USE OF LOGS

- 1.) Explorations were made by ordinary and conventional methods and with care adequate for Weston & Sampson's study and/or design purposes. The exploration logs are part of a specific report prepared by Weston & Sampson for the referenced project and client, and are an integral part of that report. Information and interpretations are subject to the explanations and limitations stated in the report. Weston & Sampson is not responsible for any interpretations, assumptions, projections, or interpolations made by others.
- 2.) Exploration logs represent general conditions observed at the point of exploration on the date(s) stated. Boundary lines separating soil and rock layers (strata) represent approximate boundaries only and are shown as solid lines where observed and dashed lines where inferred based on drilling action. Actual transitions may be gradual and changes may occur over time.
- 3.) Soil and rock descriptions are based on visual-manual examination of recovered samples, direct observation in test pits (when permissible), and laboratory testing (when conducted).
- 4.) Water level observations were made at the times and under the conditions stated. Fluctuations should be expected to vary with seasons and other factors. Use of fluids during drilling may affect water level observations. The absence of water level observations does not necessarily mean the exploration was dry or that subsurface water will not be encountered during construction.
- 5.) Standard split spoon samplers may not recover particles with any dimension larger than 1-3/8 inches. Reported gravel conditions or poor sample recovery may not reflect actual in-situ conditions.
- 6.) Sections of this guide provide a general overview of Weston & Sampson's practices and procedures for *identifying* and *describing* soil and rock. These procedures are predominantly based on ASTM D2488, *Standard Practice for Description and Identification of Soils (Visual-Manual Procedures)*, the International Society of Rock Mechanics (ISRM) standards, and the *Engineering Geology Field Manual* published by the Bureau of Reclamation. Not all aspects of this guide relating to description and identification procedures of soil and rock may be applicable in all circumstances.

SAMPLER GRAPHICS

- Split Spoon (Standard)
2" OD, 1-3/8" ID
- Split Spoon (Oversize)
3" OD, 2-3/8" ID
- Shelby or Piston Tube
3" OD, 2-7/8" ID
- Double-Tube Rock Core Barrel
2" Core Diameter
- Direct Push with Acetate Liner
Various Liner Sizes
- Auger Sample
(from cuttings or hand auger)
- Grab Sample
(manual, from discrete point)
- Composite Sample
(multiple grab samples)

WELL GRAPHICS

- Cement concrete seal around casing or riser pipe
- Bentonite seal around casing or riser pipe
- Cement grout seal around casing or riser pipe
- Soil backfill around riser pipe or beneath screen
- Gravel backfill around screen or riser pipe
- Sand backfill around screen or riser pipe (filter sand)
- Solid-wall riser; Sch. 40 PVC, 1" ID unless noted otherwise
- Slotted screen; Sch. 40 PVC, 1" ID with machined slots

CAVING / SEEPAGE TERMS

The following caving and/or seepage terms may appear on a test pit log.

Caving Term	Criteria
Minor.....	less than 1 cubic ft.
Moderate.....	1 to 3 cubic ft.
Severe.....	greater than 3 cubic ft.

Seepage Term	Criteria
Slow.....	less than 1 gpm
Moderate.....	1 to 3 gpm
Fast.....	greater than 3 gpm

KEY TO WATER LEVELS

- Observed in exploration during advancement.
- Measured in exploration at completion, prior to backfilling or well installation.
- Measured in exploration after the stated stabilization period, prior to backfilling, or in well installation if noted.

DEFINITIONS OF COMMON TERMS

Sample Recovery Ratio - The length of material recovered in a drive or push type sampler over the length of sampler penetration, in inches (e.g. 18/24).

Standard Penetration Test (SPT) - An in-situ test where a standard split-spoon sampler is driven a distance of 12 or 18 inches (after an initial 6-inch seating interval) using a 140-lb. hammer falling 30 inches for each blow.

SPT Blows - The number of hammer blows required to drive a split-spoon sampler each consecutive 6-inch interval during a *Standard Penetration Test*. If no discernable advancement of a split spoon sampler is made after 50 consecutive hammer blows, 50/X indicates *sampler refusal* and is the number of blows required to drive the sampler X inches.

SPT N-Value (N) - The uncorrected blow count representation of a soil's penetration resistance over a 12-inch interval after an initial 6-in. seating interval, reported in blows per foot (bpf). The N-value is correlated to soil engineering properties.

Auger Refusal - No discernable advancement of the auger over a period of 5 minutes with full rig down pressure applied.

Casing Refusal (Driven) - Casing penetration of less than 6 inches after a minimum 50 blows of a drop hammer weighing 300 lbs. or a minimum 100 blows of a drop hammer weighing 140 lbs.

PID Measurement - A measurement (electronic reading) taken in the field using a photoionization detector (PID) to detect the presence of volatile organic compounds in a soil sample. Values are reported as benzene equivalent units in parts per million (ppm) unless noted otherwise.

Rock Quality Designation (RQD) - A qualitative index measure of the degree of jointing and fracture of a rock core taken from a borehole. The RQD is defined as the sum length of solid core pieces 4 inches or longer divided by the run (cored) length, expressed as a percentage. Higher RQD values may indicate fewer joints and fractures in the rock mass.

Fill (Made Ground) - A deposit of soil and/or artificial waste materials that has been placed or altered by human processes.

LABORATORY TESTS AND FIELD MEASUREMENTS

MC.....	Moisture Content	IC.....	1D Incremental Consolidation
OC.....	Organic Content	VS.....	Laboratory Vane Shear
PL.....	Plastic Limit	US.....	Unconfined Compression
LL.....	Liquid Limit	TC.....	Triaxial Compression
GC.....	Gravel Content	PP.....	Pocket (Hand) Penetrometer
SC.....	Sand Content	TV.....	Torvane (Hand Vane)
FC.....	Fines Content	PID.....	Photoionization Detector
DS.....	Direct Shear	FID.....	Flame Ionization Detector

BORING ADVANCEMENT METHODS

Hollow-Stem Auger Drilling - Utilizes continuous flight auger sections with hollow stems to advance the borehole. Drill rods and a plug are inserted into the auger stem to prevent the entrance of soil cuttings into the augers.

Rotary Wash Drilling - Utilizes downward pressure and rotary action applied to a non-coring bit while washing the cuttings to the surface using a circulating fluid injected down the drill rods. The borehole is supported with either steel casing or the drilling fluid. Where a casing is used, the borehole is advanced sequentially by driving the casing to the desired depth and then cleaning out the casing. The process of driving and cleaning the casing is commonly referred to as the 'drive-and-wash' technique.

Continuous Sampling - Includes a variety of methods and procedures during which the borehole is advanced via continuous recovery of soil samples. *Direct Push* sampling is a common method that uses static downward pressure combined with percussive energy to drive a steel mandrel into the ground at continuous intervals while recovering soil samples in disposable acetate liners.

Rock Coring - Utilizes downward pressure and rotary action applied to a core barrel equipped with a diamond-set or tungsten carbide coring bit. During conventional coring, the entire barrel is retrieved from the hole upon completion of a core run. Wireline coring allows for removal of the inner barrel assembly containing the actual core while the drill rods and outer barrel remain in the hole. Various types and sizes of core barrels and bits are used.

GUIDE TO SUBSURFACE EXPLORATION LOGS



INDEX SHEET 2 SOIL DESCRIPTION

SOIL CONSTITUENTS

Naturally occurring soils consist of one or more of the following matrix constituents defined in terms of particle size.

Constituent	U.S. Sieve Size	Observed Size (in.)
Gravel (Coarse)	3/4 in. - 3 in.	3/4 - 3
Gravel (Fine)	No. 4 - 3/4 in.	1/5 - 3/4
Sand (Coarse)	No. 10 - No. 40	1/16 - 1/5
Sand (Medium)	No. 40 - No. 10	1/64 - 1/16
Sand (Fine)	No. 200 - No. 40	1/300 - 1/64
Fines (Silt or Clay)	Smaller than No. 200	Less than 1/300

SOIL IDENTIFICATION

Soil identification refers to the grouping of soils with similar physical characteristics into a category defined by a **group name** and corresponding **group symbol** based on estimation of the matrix soil constituents to the nearest 5% and simple manual tests. Proportions of cobbles, boulders, and other non-matrix soil materials are not considered during this procedure but are included in the overall soil description if observed or thought to be present. Refer to the following descriptions and tables adapted from ASTM D2488.

Coarse-Grained Soil - Coarse-grained soils contain fewer than 50% fines and are identified based on the following table.

Primary Constituent	Fines Percent	Type of Fines and Gradation	Group Symbol	Group Name ⁽¹⁾
GRAVEL % gravel > 10% % sand	≤ 5%	well graded	GW	Well graded gravel
		poorly graded	GP	Poorly graded gravel
	10% to 45%	clayey well graded	GW-GC	Well graded gravel with clay
		clayey poorly graded	GP-GC	Poorly graded gravel with clay
		silty well graded	GW-GM	Well graded gravel with silt
		silty poorly graded	GP-GM	Poorly graded gravel with silt
SAND % sand ≥ 10% % gravel	≤ 5%	clay fines	GC	Clayey gravel
		silt fines	GM	Silty gravel
	10% to 45%	well graded	SW	Well graded sand
		poorly graded	SP	Poorly graded sand
		clayey well graded	SW-SC	Well graded sand with clay
		clayey poorly graded	SP-SC	Poorly graded sand with clay
		silty well graded	SW-SM	Well graded sand with silt
		silty poorly graded	SP-SM	Poorly graded sand with silt
	15% to 45%	clay fines	SC	Clayey sand
		silt fines	SM	Silty sand

⁽¹⁾ If soil is a gravel and contains 15% or more sand, add "with sand" to the group name. If soil is a sand and contains 15% of more gravel, add "with gravel" to the group name.

Inorganic Fine-Grained Soil - Fine-grained soils contain 50% or more fines and are identified based on the following table.

Plasticity Criteria	Dry Strength	Coarse Fraction S = Sand, G = Gravel	Group Symbol	Group Name ⁽¹⁾
Medium	Medium to high	< 15% S + G	CL	Lean clay
		≥ 30% % S ≥ % G	CL	Sandy lean clay
		S + G % S < % G	CL	Gravelly lean clay
Non-plastic	None to low	< 15% S + G	ML	Silt
		≥ 30% % S ≥ % G	ML	Sandy silt
		S + G % S < % G	ML	Gravelly silt
High	High to very high	< 15% S + G	CH	Fat clay
		≥ 30% % S ≥ % G	CH	Sandy fat clay
		S + G % S < % G	CH	Gravelly fat clay
Low to Medium	Low to medium	< 15% S + G	MH	Elastic silt
		≥ 30% % S ≥ % G	MH	Sandy elastic silt
		S + G % S < % G	MH	Gravelly elastic silt

⁽¹⁾ If soil contains 15% to 25% sand or gravel, add "with sand" or "with gravel" to the group name.

Organic Fine-Grained Soil - Fine-grained soils that contain enough organic particles to influence the soil properties are identified as Organic Soil and assigned the group symbol OL or OH.

Highly Organic Soil (Peat) - Soils composed primarily of plant remains in various stages of decomposition are identified as Peat and given the group symbol PT. Peat usually has an organic odor, a dark brown to black color, and a texture ranging from fibrous (original plant structure intact or mostly intact) to amorphous (plant structure decomposed to fine particles).

SOIL DESCRIPTION

Soils are described in the following general sequence. Deviations may occur in some instances.

Identification Components

(1) Group Name and Group Symbol

Description Components

- (2) Consistency (Fine-Grained) or Apparent Density (Coarse-Grained)
- (3) Color (*note, the term "to" may be used to indicate a gradational change*)
- (4) Soil Moisture
- (5) Matrix Soil Constituents (Gravel, Sand, Fines)
 - ↳ Proportion (*by weight*), particle size, plasticity of fines, angularity, etc.
- (6) Non-Matrix Soil Materials and Proportions (*by volume*)
- (7) Other Descriptive Information (Unusual Odor, Structure, Texture, etc.)
- (8) [Geologic Formation Name or Soil Survey Unit]

SPT N-VALUE CORRELATIONS

Consistency	SPT N-Value	Apparent Density	SPT N-Value
Very soft	0 - 2	Very loose	0 - 5
Soft	2 - 4	Loose	5 - 10
Medium stiff	4 - 8	Medium dense	10 - 30
Stiff	8 - 15	Dense	30 - 50
Very stiff	15 - 30	Very dense	> 50
Hard	> 30		

SOIL MOISTURE

Dry..... Apparent absence of moisture; dry to the touch.
Moist..... Damp but no visible water.
Wet..... Visible free water; saturated.

PROPORTIONS / PERCENTAGES

Proportions of gravel, sand, and fines (excluding cobbles, boulders, and other constituents) are stated in the following terms indicating a range of percentages by weight (to nearest 5%) of the minus 3-in. soil fraction and add up to 100%.

Proportions of cobbles, boulders, and other non-matrix soil materials including artificial debris, roots, plant fibers, etc. are stated in the following terms indicating a range of percentages by volume (to the nearest 5%) of the total soil.

Mostly	50% - 100%	Numerous	40% - 50%
Some	30% - 45%	Common	25% - 35%
Little	15% - 25%	Occasional	10% - 20%
Few	5% - 10%	Trace	Less than 5%
Trace	Less than 5%		

PLASTICITY (FINES ONLY)

Non-plastic..... Dry specimen ball falls apart easily. Cannot be rolled into thread at any moisture content.

Low..... Dry specimen ball easily crushed with fingers. Can be rolled into 1/8-in. thread with some difficulty.

Medium..... Difficult to crush dry specimen ball with fingers. Easily rolled into 1/8-in. thread.

High..... Cannot crush dry specimen ball with fingers. Easily rolled and re-rolled into 1/8-in. thread.


COBBLES AND BOULDERS

Cobbles - Particles of rock that will pass a 12-in. square opening and be retained on a 3-in. sieve.

Boulders - Particles of rock that will not pass a 12-in. square opening.


Note: Where the percentage (by volume) of cobbles and/or boulders cannot be accurately or reliably estimated, the terms "with cobbles", "with boulders", or "with cobbles and boulders" may be used to indicate observed or inferred presence.

CONTRACTOR:	Desmond Well Drilling, Inc.	BORING LOCATION:	See Attached Figure	DATE START:	April 16, 2025
FOREMAN:	Pat Desmond	ADVANCE METHOD:	Hollow-Stem Auger Drilling	DATE FINISH:	April 16, 2025
LOGGED BY:	Aaron Chabot	AUGER DIAMETER:	4-1/4" ID (Stem), 7-5/8" OD (Flights)	GROUND EL:	121.0 ± (NAVD88)
CHECKED BY:	Stephen Spink	SUPPORT CASING:	N/A	FINAL DEPTH:	39.0 ft.
EQUIPMENT:	CME 45, Truck Mounted	CORING METHOD:	N/A	GRID COORDS:	N:2828052.0 ± / E:1048383.8 ±
SPT HAMMER:	Automatic (140-lb.)	BACKFILL MATERIAL:	Drill Cuttings	GRID SYSTEM:	NAD83 State Plane (MA)




DEPTH BELOW GROUND SURFACE [VERTICAL FT.]	SAMPLE TYPE GRAPHIC	SAMPLE ID NUMBER AND RECOVERY RATIO [IN./IN.]	SPT BLOWS / 6 IN. (OR) CORE RATE / 12 IN. [MIN.]	GEOTECHNICAL TEST DATA				STRATIGRAPHY LOG	STRATUM IDENTIFICATION AND DESCRIPTION	ELEVATION SCALE SHOWN TO NEAREST FT.	REMARKS, OTHER TESTS, AND INSTALLATIONS
				● N-Value, Raw (bpf)							
				☒ Organic Content (%)							
				⊕ Moisture Content (%)							
				10	20	30	40				
				25	50	75	100				
				▶ Plastic Limit, PL (%)							
				▲ Liquid Limit, LL (%)							

CONTRACTOR:	Desmond Well Drilling, Inc.	BORING LOCATION:	See Attached Figure	DATE START:	April 16, 2025
FOREMAN:	Pat Desmond	ADVANCE METHOD:	Hollow-Stem Auger Drilling	DATE FINISH:	April 16, 2025
LOGGED BY:	Aaron Chabot	AUGER DIAMETER:	4-1/4" ID (Stem), 7-5/8" OD (Flights)	GROUND EL:	121.0 ± (NAVD88)
CHECKED BY:	Stephen Spink	SUPPORT CASING:	N/A	FINAL DEPTH:	39.0 ft.
EQUIPMENT:	CME 45, Truck Mounted	CORING METHOD:	N/A	GRID COORDS:	N:2828167.6 ± / E:1048540.8 ±
SPT HAMMER:	Automatic (140-lb.)	BACKFILL MATERIAL:	Drill Cuttings	GRID SYSTEM:	NAD83 State Plane (MA)



DEPTH BELOW GROUND SURFACE [VERTICAL FT.]	SAMPLE TYPE GRAPHIC	SAMPLE ID NUMBER AND RECOVERY RATIO [IN./IN.]	SPT BLOWS / 6 IN. (OR) CORE RATE / 12 IN. [MIN.]	GEOTECHNICAL TEST DATA				STRATIGRAPHY LOG	STRATUM IDENTIFICATION AND DESCRIPTION	ELEVATION SCALE SHOWN TO NEAREST FT.	REMARKS, OTHER TESTS, AND INSTALLATIONS	
				● N-Value, Raw (bpf)	☒ Organic Content (%)						Note: Values in brackets preceeding a remark indicate depth below ground surface (in feet) corresponding to the remark.	
				⊕ Moisture Content (%)	▶ Plastic Limit, PL (%)	▲ Liquid Limit, LL (%)						
				25	50	75	100					


CONTRACTOR:	Desmond Well Drilling, Inc.	BORING LOCATION:	See Attached Figure	DATE START:	April 15, 2025
FOREMAN:	Pat Desmond	ADVANCE METHOD:	Hollow-Stem Auger Drilling	DATE FINISH:	April 15, 2025
LOGGED BY:	Aaron Chabot	AUGER DIAMETER:	4-1/4" ID (Stem), 7-5/8" OD (Flights)	GROUND EL:	122.5 ± (NAVD88)
CHECKED BY:	Stephen Spink	SUPPORT CASING:	N/A	FINAL DEPTH:	39.0 ft.
EQUIPMENT:	CME 45, Truck Mounted	CORING METHOD:	N/A	GRID COORDS:	N:2828056.7 ± / E:1048574.5 ±
SPT HAMMER:	Automatic (140-lb.)	BACKFILL MATERIAL:	Drill Cuttings and Asphalt Patch	GRID SYSTEM:	NAD83 State Plane (MA)



Refer to the attached index sheets for important information about this log including general notes, legends, and guidance on description methods and procedures.


DEPTH BELOW GROUND SURFACE [VERTICAL FT.]	SAMPLE TYPE GRAPHIC	SAMPLE ID NUMBER AND RECOVERY RATIO [IN./IN.]	SPT BLOWS / 6 IN. (OR) CORE RATE / 12 IN. [MIN.]	GEOTECHNICAL TEST DATA				STRATIGRAPHY LOG	STRATUM IDENTIFICATION AND DESCRIPTION	ELEVATION SCALE SHOWN TO NEAREST FT.	REMARKS, OTHER TESTS, AND INSTALLATIONS
				10	20	30	40				
				25	50	75	100				
				⊕ Moisture Content (%)							
				▶ Plastic Limit, PL (%)							
				▲ Liquid Limit, LL (%)							
								</			

CONTRACTOR: Desmond Well Drilling, Inc.	BORING LOCATION: See Attached Figure	DATE START: April 15, 2025
FOREMAN: Pat Desmond	ADVANCE METHOD: Hollow-Stem Auger Drilling	DATE FINISH: April 15, 2025
LOGGED BY: Aaron Chabot	AUGER DIAMETER: 4-1/4" ID (Stem), 7-5/8" OD (Flights)	GROUND EL: 124.0 ± (NAVD88)
CHECKED BY: Stephen Spink	SUPPORT CASING: N/A	FINAL DEPTH: 34.0 ft.
EQUIPMENT: CME 45, Truck Mounted	CORING METHOD: N/A	GRID COORDS: N:2827922.3 ± / E:1048496.1 ±
SPT HAMMER: Automatic (140-lb.)	BACKFILL MATERIAL: Drill Cuttings	GRID SYSTEM: NAD83 State Plane (MA)




Refer to the attached index sheets for important information about this log including general notes, legends, and guidance on description methods and procedures.

CONTRACTOR: Desmond Well Drilling, Inc.	BORING LOCATION: See Attached Figure	DATE START: April 15, 2025
FOREMAN: Pat Desmond	ADVANCE METHOD: Hollow-Stem Auger Drilling	DATE FINISH: April 15, 2025
LOGGED BY: Aaron Chabot	AUGER DIAMETER: 4-1/4" ID (Stem), 7-5/8" OD (Flights)	GROUND EL: 124.0 ± (NAVD88)
CHECKED BY: Stephen Spink	SUPPORT CASING: N/A	FINAL DEPTH: 39.0 ft.
EQUIPMENT: CME 45, Truck Mounted	CORING METHOD: N/A	GRID COORDS: N:2827852.4 ± / E:1048544.3 ±
SPT HAMMER: Automatic (140-lb.)	BACKFILL MATERIAL: Drill Cuttings	GRID SYSTEM: NAD83 State Plane (MA)



DEPTH BELOW GROUND SURFACE [VERTICAL FT.]	SAMPLE TYPE GRAPHIC	SAMPLE ID NUMBER AND RECOVERY RATIO [IN./IN.]	SPT BLOWS / 6 IN. (OR) CORE RATE / 12 IN. [MIN.]	GEOTECHNICAL TEST DATA				STRATIGRAPHY LOG	STRATUM IDENTIFICATION AND DESCRIPTION	ELEVATION SCALE SHOWN TO NEAREST FT.	REMARKS, OTHER TESTS, AND INSTALLATIONS
				● N-Value, Raw (bpf)							
				☒ Organic Content (%)							
				⊕ Moisture Content (%) ▶ Plastic Limit, PL (%) ▲ Liquid Limit, LL (%)							
				10	20	30	40				
				25	50	75	100				

CONTRACTOR:	Desmond Well Drilling, Inc.	BORING LOCATION:	See Attached Figure	DATE START:	April 16, 2025
FOREMAN:	Pat Desmond	ADVANCE METHOD:	Hollow-Stem Auger Drilling	DATE FINISH:	April 16, 2025
LOGGED BY:	Aaron Chabot	AUGER DIAMETER:	4-1/4" ID (Stem), 7-5/8" OD (Flights)	GROUND EL:	122.0 ± (NAVD88)
CHECKED BY:	Stephen Spink	SUPPORT CASING:	N/A	FINAL DEPTH:	29.0 ft.
EQUIPMENT:	CME 45, Truck Mounted	CORING METHOD:	N/A	GRID COORDS:	N:2827945.1 ± / E:1048637.9 ±
SPT HAMMER:	Automatic (140-lb.)	BACKFILL MATERIAL:	Drill Cuttings and Asphalt Patch	GRID SYSTEM:	NAD83 State Plane (MA)



Refer to the attached index sheets for important information about this log including general notes, legends, and guidance on description methods and procedures.

APPENDIX C

Geotechnical Laboratory Test Results

	195 Frances Avenue Cranston RI, 02910 Phone: (401)-467-6454 Fax: (401)-467-2398 cts.thielsch.com <i>Let's Build a Solid Foundation</i>	Client Information:	Project Information:
		Weston & Sampson Foxborough, MA (508) 698-3034 Project Contact: Stephen Spink Collected By: AJC	Truro DPW 17 Town Hall Road, Truro MA Project Number: ENG24-1552 Summary Page: 1 of 1 Report Date: 5/28/2025

LABORATORY TESTING DATA SHEET, Report No.: 7425-E-163

Boring No.	Sample ID	Depth (ft)	Laboratory No.	Identification Tests										Proctor / CBR / Permeability Tests							Laboratory Log and Soil Description
				As Rcvd Moisture Content %	LL %	PL %	OD LL	Gravel %	Sand %	Fines %	Org. %	pH	9 _d MAX (pcf) W _{opt} (%)	9 _d MAX (pcf) W _{opt} (%) (Corr.)	Dry unit wt. (pcf)	Test Moisture Content %	Target Test Setup as % of Proctor	CBR @ 0.1"	CBR @ 0.2"	Permeability cm/sec	
				D2216	D4318			D6913			D2974	D4792	D1557								
B-1	S-2	2-4	25-S-1782					8.8	83.4	7.8											Brown f-m SAND, trace f-c Gravel, trace Silt
B-1	S-9	16-18	25-S-1783					0.2	98.3	1.5											Light Brown f-m SAND, trace Silt
B-2	S-4	6-8	25-S-1784					0.7	97.7	1.6											Light Brown f-m SAND, trace Silt
B-3	S-2	2-4	25-S-1785					1.0	95.5	3.5											Light Brown f-m SAND, trace Silt, trace fine Gravel
B-5	S-5	12-14	25-S-1786					0.3	98.6	1.1											Light Brown f-m SAND, trace Silt
B-6	S-4	7-9	25-S-1787					0.7	98.2	1.1											Light Brown f-m SAND, trace Silt

Date Received:
5/20/2025


Reviewed By:


Date Reviewed:
5/28/2025

This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.
This report shall not be reproduced, except in full, without prior written approval from the Agency, as defined in ASTM E329.

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	4.1	4.7	5.7	51.6	26.1	7.8	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
1"	100.0		
3/4"	95.9		
1/2"	94.7		
3/8"	94.7		
#4	91.2		
#10	85.5		
#20	66.6		
#40	33.9		
#60	18.6		
#100	12.1		
#200	7.8		

* (no specification provided)

Soil Description
Brown f-m SAND, trace f-c Gravel, trace Silt

PL= NP Atterberg Limits LL= NV PI= NP

Coefficients
D₉₀= 3.6105 D₈₅= 1.9265 D₆₀= 0.7252
D₅₀= 0.5952 D₃₀= 0.3813 D₁₅= 0.1995
D₁₀= 0.1123 C_u= 6.45 C_c= 1.78

Classification
USCS= SW-SM AASHTO= A-1-b

Remarks

Source of Sample: Boring Depth: 2-4'
Sample Number: B-1 / S-2

Date: 5.27.25

Thielsch Engineering Inc.

Cranston, RI

Client: Weston & Sampson
Project: Truro DPW
17 Town Hall Rd, Truro MA

Project No: ENG24-1552


Fig. 25-S-1782

Tested By: TG

Checked By: Kris Roland

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.2	1.8	52.1	44.4	1.5	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8"	100.0		
#4	99.8		
#10	98.0		
#20	82.2		
#40	45.9		
#60	22.5		
#100	5.8		
#200	1.5		

* (no specification provided)

Soil Description
Light Brown f-m SAND, trace Silt

PL= NP Atterberg Limits LL= NV PI= NP

Coefficients
D₉₀= 1.1121 D₈₅= 0.9255 D₆₀= 0.5502
D₅₀= 0.4608 D₃₀= 0.3005 D₁₅= 0.2054
D₁₀= 0.1773 C_u= 3.10 C_c= 0.93

USCS= SP Classification AASHTO= A-1-b

Remarks

Source of Sample: Boring Depth: 16-18'
Sample Number: B-1 / S-9

Date: 5.27.25

Thielsch Engineering Inc.

Cranston, RI

Client: Weston & Sampson
Project: Truro DPW
17 Town Hall Rd, Truro MA

Project No: ENG24-1552


Fig. 25-S-1783

Tested By: TG

Checked By: Kris Roland

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.7	3.1	54.4	40.2	1.6	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
1/2"	100.0		
3/8"	99.7		
#4	99.3		
#10	96.2		
#20	77.9		
#40	41.8		
#60	15.5		
#100	6.7		
#200	1.6		

* (no specification provided)

Soil Description
Light Brown f-m SAND, trace Silt

PL= NP Atterberg Limits LL= NV PI= NP
Coefficients
D₉₀= 1.3126 D₈₅= 1.0612 D₆₀= 0.5899
D₅₀= 0.4951 D₃₀= 0.3416 D₁₅= 0.2461
D₁₀= 0.1969 C_u= 3.00 C_c= 1.00
Classification
USCS= SP AASHTO= A-1-b
Remarks

Source of Sample: Boring Depth: 6-8'
Sample Number: B-2 / S-4

Date: 5.27.25

Thielsch Engineering Inc.

Cranston, RI


Client: Weston & Sampson
Project: Truro DPW
17 Town Hall Rd, Truro MA
Project No: ENG24-1552

Fig. 25-S-1784

Tested By: TG Checked By: Kris Roland


These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.

Particle Size Distribution Report



These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspected and/or tested. No warranty, expressed or implied, is made.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.3	1.5	62.0	35.1	1.1	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8"	100.0		
#4	99.7		
#10	98.2		
#20	78.6		
#40	36.2		
#60	10.7		
#100	2.8		
#200	1.1		

* (no specification provided)

Soil Description
Light Brown f-m SAND, trace Silt

PL= NP Atterberg Limits LL= NV PI= NP
Coefficients
D₉₀= 1.1871 D₈₅= 1.0066 D₆₀= 0.6148
D₅₀= 0.5304 D₃₀= 0.3796 D₁₅= 0.2809
D₁₀= 0.2445 C_u= 2.51 C_c= 0.96

USCS= SP Classification AASHTO= A-1-b
Remarks

Source of Sample: Boring Depth: 12-14'
Sample Number: B-5 / S-5

Date: 5.27.25

Thielsch Engineering Inc.

Cranston, RI


Client: Weston & Sampson
Project: Truro DPW
17 Town Hall Rd, Truro MA
Project No: ENG24-1552

Fig. 25-S-1786

Tested By: TG Checked By: Kris Roland

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspected and/or tested. No warranty, expressed or implied, is made.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.7	3.0	75.4	19.8	1.1	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/8"	100.0		
#4	99.3		
#10	96.3		
#20	65.2		
#40	20.9		
#60	5.5		
#100	2.1		
#200	1.1		

* (no specification provided)

Soil Description
Light Brown f-m SAND, trace Silt

PL= NP Atterberg Limits LL= NV PI= NP
Coefficients
D₉₀= 1.4980 D₈₅= 1.3029 D₆₀= 0.7736
D₅₀= 0.6652 D₃₀= 0.4995 D₁₅= 0.3669
D₁₀= 0.3097 C_u= 2.50 C_c= 1.04

USCS= SP Classification AASHTO= A-1-b
Remarks

Source of Sample: Boring Depth: 7-9'
Sample Number: B-6 / S-4

Date: 05.27.25

Thielsch Engineering Inc.

Cranston, RI

Client: Weston & Sampson
Project: Truro DPW
17 Town Hall Rd, Truro MA
Project No: ENG24-1552

Fig. 25-S-1787

Tested By: TG Checked By: Kris Roland

APPENDIX D

“Important Information about This Geotechnical-Engineering Report,” by GBA, Inc.

Important Information about This Geotechnical-Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

The Geoprofessional Business Association (GBA) has prepared this advisory to help you – assumedly a client representative – interpret and apply this geotechnical-engineering report as effectively as possible. In that way, you can benefit from a lowered exposure to problems associated with subsurface conditions at project sites and development of them that, for decades, have been a principal cause of construction delays, cost overruns, claims, and disputes. If you have questions or want more information about any of the issues discussed herein, contact your GBA-member geotechnical engineer. Active engagement in GBA exposes geotechnical engineers to a wide array of risk-confrontation techniques that can be of genuine benefit for everyone involved with a construction project.

Understand the Geotechnical-Engineering Services Provided for this Report

Geotechnical-engineering services typically include the planning, collection, interpretation, and analysis of exploratory data from widely spaced borings and/or test pits. Field data are combined with results from laboratory tests of soil and rock samples obtained from field exploration (if applicable), observations made during site reconnaissance, and historical information to form one or more models of the expected subsurface conditions beneath the site. Local geology and alterations of the site surface and subsurface by previous and proposed construction are also important considerations. Geotechnical engineers apply their engineering training, experience, and judgment to adapt the requirements of the prospective project to the subsurface model(s). Estimates are made of the subsurface conditions that will likely be exposed during construction as well as the expected performance of foundations and other structures being planned and/or affected by construction activities.

The culmination of these geotechnical-engineering services is typically a geotechnical-engineering report providing the data obtained, a discussion of the subsurface model(s), the engineering and geologic engineering assessments and analyses made, and the recommendations developed to satisfy the given requirements of the project. These reports may be titled investigations, explorations, studies, assessments, or evaluations. Regardless of the title used, the geotechnical-engineering report is an engineering interpretation of the subsurface conditions within the context of the project and does not represent a close examination, systematic inquiry, or thorough investigation of all site and subsurface conditions.

Geotechnical-Engineering Services are Performed for Specific Purposes, Persons, and Projects, and At Specific Times

Geotechnical engineers structure their services to meet the specific needs, goals, and risk management preferences of their clients. A geotechnical-engineering study conducted for a given civil engineer

will not likely meet the needs of a civil-works constructor or even a different civil engineer. Because each geotechnical-engineering study is unique, each geotechnical-engineering report is unique, prepared *solely* for the client.

Likewise, geotechnical-engineering services are performed for a specific project and purpose. For example, it is unlikely that a geotechnical-engineering study for a refrigerated warehouse will be the same as one prepared for a parking garage; and a few borings drilled during a preliminary study to evaluate site feasibility will not be adequate to develop geotechnical design recommendations for the project.

Do not rely on this report if your geotechnical engineer prepared it:

- for a different client;
- for a different project or purpose;
- for a different site (that may or may not include all or a portion of the original site); or
- before important events occurred at the site or adjacent to it; e.g., man-made events like construction or environmental remediation, or natural events like floods, droughts, earthquakes, or groundwater fluctuations.

Note, too, the reliability of a geotechnical-engineering report can be affected by the passage of time, because of factors like changed subsurface conditions; new or modified codes, standards, or regulations; or new techniques or tools. *If you are the least bit uncertain about the continued reliability of this report, contact your geotechnical engineer before applying the recommendations in it. A minor amount of additional testing or analysis after the passage of time – if any is required at all – could prevent major problems.*

Read this Report in Full

Costly problems have occurred because those relying on a geotechnical-engineering report did not read the report in its entirety. Do not rely on an executive summary. Do not read selective elements only. *Read and refer to the report in full.*

You Need to Inform Your Geotechnical Engineer About Change

Your geotechnical engineer considered unique, project-specific factors when developing the scope of study behind this report and developing the confirmation-dependent recommendations the report conveys. Typical changes that could erode the reliability of this report include those that affect:

- the site's size or shape;
- the elevation, configuration, location, orientation, function or weight of the proposed structure and the desired performance criteria;
- the composition of the design team; or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project or site changes – even minor ones – and request an assessment of their impact. *The geotechnical engineer who prepared this report cannot accept*

responsibility or liability for problems that arise because the geotechnical engineer was not informed about developments the engineer otherwise would have considered.

Most of the “Findings” Related in This Report Are Professional Opinions

Before construction begins, geotechnical engineers explore a site’s subsurface using various sampling and testing procedures. *Geotechnical engineers can observe actual subsurface conditions only at those specific locations where sampling and testing is performed.* The data derived from that sampling and testing were reviewed by your geotechnical engineer, who then applied professional judgement to form opinions about subsurface conditions throughout the site. Actual site-wide subsurface conditions may differ – maybe significantly – from those indicated in this report. Confront that risk by retaining your geotechnical engineer to serve on the design team through project completion to obtain informed guidance quickly, whenever needed.

This Report’s Recommendations Are Confirmation-Dependent

The recommendations included in this report – including any options or alternatives – are confirmation-dependent. In other words, they are not final, because the geotechnical engineer who developed them relied heavily on judgement and opinion to do so. Your geotechnical engineer can finalize the recommendations *only after observing actual subsurface conditions* exposed during construction. If through observation your geotechnical engineer confirms that the conditions assumed to exist actually do exist, the recommendations can be relied upon, assuming no other changes have occurred. *The geotechnical engineer who prepared this report cannot assume responsibility or liability for confirmation-dependent recommendations if you fail to retain that engineer to perform construction observation.*

This Report Could Be Misinterpreted

Other design professionals’ misinterpretation of geotechnical-engineering reports has resulted in costly problems. Confront that risk by having your geotechnical engineer serve as a continuing member of the design team, to:

- confer with other design-team members;
- help develop specifications;
- review pertinent elements of other design professionals’ plans and specifications; and
- be available whenever geotechnical-engineering guidance is needed.

You should also confront the risk of constructors misinterpreting this report. Do so by retaining your geotechnical engineer to participate in prebid and preconstruction conferences and to perform construction-phase observations.

Give Constructors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can shift unanticipated-subsurface-conditions liability to constructors by limiting the information they provide for bid preparation. To help prevent the costly, contentious problems this practice has caused, include the complete geotechnical-engineering report, along with any attachments or appendices, with your contract documents, *but be certain to note*

conspicuously that you’ve included the material for information purposes only. To avoid misunderstanding, you may also want to note that “informational purposes” means constructors have no right to rely on the interpretations, opinions, conclusions, or recommendations in the report. Be certain that constructors know they may learn about specific project requirements, including options selected from the report, *only* from the design drawings and specifications. Remind constructors that they may perform their own studies if they want to, and *be sure to allow enough time* to permit them to do so. Only then might you be in a position to give constructors the information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions. Conducting prebid and preconstruction conferences can also be valuable in this respect.

Read Responsibility Provisions Closely

Some client representatives, design professionals, and constructors do not realize that geotechnical engineering is far less exact than other engineering disciplines. This happens in part because soil and rock on project sites are typically heterogeneous and not manufactured materials with well-defined engineering properties like steel and concrete. That lack of understanding has nurtured unrealistic expectations that have resulted in disappointments, delays, cost overruns, claims, and disputes. To confront that risk, geotechnical engineers commonly include explanatory provisions in their reports. Sometimes labeled “limitations,” many of these provisions indicate where geotechnical engineers’ responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely.* Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The personnel, equipment, and techniques used to perform an environmental study – e.g., a “phase-one” or “phase-two” environmental site assessment – differ significantly from those used to perform a geotechnical-engineering study. For that reason, a geotechnical-engineering report does not usually provide environmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated subsurface environmental problems have led to project failures.* If you have not obtained your own environmental information about the project site, ask your geotechnical consultant for a recommendation on how to find environmental risk-management guidance.

Obtain Professional Assistance to Deal with Moisture Infiltration and Mold

While your geotechnical engineer may have addressed groundwater, water infiltration, or similar issues in this report, the engineer’s services were not designed, conducted, or intended to prevent migration of moisture – including water vapor – from the soil through building slabs and walls and into the building interior, where it can cause mold growth and material-performance deficiencies. Accordingly, *proper implementation of the geotechnical engineer’s recommendations will not of itself be sufficient to prevent moisture infiltration.* Confront the risk of moisture infiltration by including building-envelope or mold specialists on the design team. *Geotechnical engineers are not building-envelope or mold specialists.*



**GEOPROFESSIONAL
BUSINESS
ASSOCIATION**

Telephone: 301/565-2733

e-mail: info@geoprofessional.org www.geoprofessional.org

May 29, 2025

Jarrold Cabral
DPW Director
17 Town Hall Road
Truro, MA 02666

RE: Report of Hazardous Building Materials Investigation
17 Town Hall Road
Truro, MA 02666

Dear Mr. Cabral,

INTRODUCTION

Weston & Sampson Engineers, Inc. (Weston & Sampson) is pleased to present this report of our Hazardous Building Materials Investigation (HBMI) services associated with the Truro Department of Public Works (DPW) building located at 17 Town Hall Road in Truro, Massachusetts (the Site). Our services were completed in accordance with our agreement. In response to the proposed renovation activities at the Site, Weston & Sampson performed a survey to identify asbestos-containing materials (ACMs), lead based paints/coatings, and other hazardous materials (OHMs) within the renovation area.

SITE DESCRIPTION

The Truro DPW is composed of three main structures each with distinct separate areas. The southernmost structure is a four-bay garage with an office and storage addition on the rear and two storage sheds on the West. The four-bay garage and additions share a roof with seemingly three types of shingles, only one of which being accessible to sample. The approximate footprint of the 4-bay garage with additions is 3,500 SF. In the center of site is a salt shed with a footprint of approximately 3,000 SF with two garages on either side, each with an approximate footprint of 1750 SF and shingled roofing on both the salt shed and garages. The Northernmost structure has an approximate footprint of 3,000 and is composed of six different buildings. Starting from West to East the buildings are as follows: Shop office, Shop, Two-bay garage, Shed, Office, and Office addition. The Two-bay garage has an EPDM roof while the others are shingled.

SURVEY RESULTS

Asbestos Survey

The asbestos survey was performed by Massachusetts-licensed asbestos inspector Mr. Caleb Pettigrew (license No.: AI901112) on May 9th, 2025. A total of 101 samples of suspect asbestos-containing materials were collected from 50 homogenous materials. We performed the bulk sampling in the subject area according to methods outlined in the U.S. Environmental Protection Agency (EPA) guidance document titled, "Guidance for Controlling Asbestos-Containing Materials in Buildings" (Document No. 560/5-85/024). Samples were analyzed by EMSL Analytical, Inc. in Woburn, Massachusetts. The results of the sampling are summarized below.

Asbestos Sample Results

Client ID	Description	Location	Analytical Result (% Asbestos)
01A-B	Tan carpet mastic	Office Closet	NAD
02A-C	White leveling compound	Office Closet	NAD
03A-B	Wall sheetrock	Office Bathroom	NAD
04A-B	Joint compound	Office Bathroom	NAD
05A-B	Grey sink caulk	Office Bathroom	NAD
06A-B	Building paper	Office Exterior	NAD
07A-B	Tan caulk on door wood to concrete	2-Bay Garage Exterior	NAD
08A-B	White window glazing	2-Bay Garage Exterior	NAD
09A-B	White caulk on door wood to wood	2-Bay Garage Exterior	NAD
10A-B	White window glazing	2-Bay Garage Interior	NAD
11A-B	White window caulk	Shop Exterior	NAD
12A-B	White door caulk	Shop Office Exterior	NAD
13A-B	Building paper	Shop Office Exterior	NAD
14A-B	Red shingle	Shed Exterior	NAD
15A-B	Black foundation damp proofing	Salt Shed Garage Exterior	NAD
16A-B	Black rafter sealant	Salt Shed Garage Interior	NAD
17A-B	Roof shingle	Shed Exterior	NAD
18A-B	Grey caulk	Concrete Shed Exterior	NAD
19A-B	White window glazing	Concrete Shed Exterior	NAD
20A-B	White caulk	Concrete Shed Interior	NAD
21A-B	White window glazing	4-Bay Garage Exterior	NAD
22A-B	Corner white caulk	4-Bay Garage Exterior	NAD
23A-B	White window caulk	4-Bay Garage Exterior	NAD
24A-B	Roof shingle	Shed	NAD
25A-B	Expansion Joint	4-Bay Garage Interior	NAD
26A-B	Sink undercoat	4-Bay Garage Office	NAD
27A-B	Black mastic on wall	4-Bay Garage Office	NAD
28A-B	Sheetrock	4-Bay Garage Office	NAD
29A-B	Joint compound	4-Bay Garage Office	NAD
30A-B	Grey window caulk	4-Bay Garage Bathroom	NAD
31A-B	Sheetrock	4-Bay Garage Boiler Room	NAD
32A-B	Joint compound	4-Bay Garage Boiler Room	NAD

Client ID	Description	Location	Analytical Result (% Asbestos)
33A-B	Ceiling panel	4-Bay Garage Interior	NAD
34A-B	Black building paper	4-Bay Garage Attic	NAD
35A-B	Roof shingle	4-Bay Garage Exterior	NAD
36A-B	Roof paper	4-Bay Garage Exterior	NAD
37A-B	Roof shingle	Shop Office Shed	NAD
38A-B	White roof trim caulk	Shop/Shop Office Exterior	NAD
39A-B	Black caulk	Shop Exterior	NAD
40A-B	Roof shingle	Shop Office Exterior	NAD
41A-B	White caulk	Shop Office Exterior	NAD
42A-B	Roof shingle	Shop Exterior	NAD
43A-B	Tan seam sealant	Shop/2-Bay Garage Exterior	NAD
44A-B	Ceiling sheetrock	2-Bay Garage Interior	NAD
45A-B	Roof shingle	Office Exterior	NAD
46A-B	Roof paper	Office Exterior	NAD
47A-B	Roof shingle	Office Addition Exterior	NAD
48A-B	Roof paper	Office Addition Exterior	NAD
49A-B	Foundation damp proofing	TP-7 (4-Bay Garage Exterior)	NAD
50A-B	Addition foundation damp proofing	TP-7 (4-Bay Garage Exterior)	NAD

NAD=no asbestos detected

The EPA and Massachusetts Department of Environmental Protection (MassDEP), consider materials identified to contain greater than or equal to 1% asbestos to be ACMs. As shown in the tables above, none of the building materials sampled by Weston & Sampson contained asbestos exceeding 1%. According to MassDEP regulations, ACMs must be removed by a licensed contractor prior to any activity that would disturb the material.

Asbestos Limitations

Our survey was limited to the building area scheduled to be renovated. Our survey did not include an evaluation of materials of soils or underground materials that may be present at the Site. Limited exploratory demolition was performed to access potentially hidden materials. Other suspect ACMs may be present at the Site outside the survey area or within other building areas that may not have been accessible by Weston & Sampson during our survey. ACMs must be removed by a licensed contractor prior to any activity that would disturb the material. Weston & Sampson recommends that if any suspect materials are uncovered during demolition or renovation activities that were not identified during the survey, that the materials be sampled and analyzed for asbestos content prior to disturbance. This document is not intended to be nor will it suffice to serve as a bid document or specification.

Per MassDEP regulations, the owner/operator must maintain a copy of this written asbestos survey report at the subject facility for at least two years. If the facility is unstaffed or if it is demolished, the owner/operator must maintain a copy at their regular place of business.

Lead Paint Screening

As part of the HBMI, Weston & Sampson performed a lead paint screening of the site buildings. During the screening, we collected eight (8) paint chip samples from representative painted/coated building components for analysis via Atomic Absorption Spectrometry using method SW846-3050B. Samples were analyzed by EMSL Analytical, Inc. of Orlando, Florida.

The paint screening revealed that one of the paint chip samples collected from the renovation area contained levels of lead paint greater than the EPA residential standard of 0.50% lead by weight. However, the Occupational Health and Safety Administration (OSHA) Lead in Construction Standard 29 CFR 1926.62 considers *any* detectable level of lead to be a potential for exposure if dust is generated from disturbances of surfaces coated with paint containing lead.

Lead Paint Sample Results

Sample ID	Sample Description	Analytical Results (% lead by weight)
L1	Office Bathroom-Light blue wall paint	<0.0081 % wt
L2	Office Exterior-White trim paint	11.9 % wt
L3	2-Bay Garage Exterior-Grey/green paint	0.147 % wt
L4	Shop Office Exterior-Green paint	<0.0064 % wt
L5	Sale Shed Garage Exterior-Grey paint	<0.0064 % wt
L6	4-Bay Garage Exterior-Grey paint	0.0105 % wt
L7	4-Bay Garage Interior-Office white wall	<0.0064 % wt
L8	4-Bay Garage Interior-White paint	<0.0064 % wt

Regulatory Implications and Regulations

OSHA defines any detectable concentration of lead in paint as a potential lead exposure hazard to workers doing construction/demolition-type work on these surfaces as even small concentrations of lead can result in unacceptable employee exposures depending upon the method of removal and other workplace conditions. Since these conditions can vary greatly, the lead-in-construction standard was written to require exposure monitoring or the use of historical or objective data to ensure that employee exposures do not exceed the Action Level of 30 micrograms per cubic meter of air ($\mu\text{g}/\text{m}^3$). Historical data may be applied to some construction tasks involving lead.

OSHA requires that if coated surfaces with paint containing lead are impacted during demolition, then lead exposure monitoring must be performed by the contractor. Contractors and employers of staff who may disturb these materials are obligated to perform a 'negative exposure assessment' in accordance with OSHA regulations in order to document that, although minimal levels of lead are present in these materials, exposure to lead does not exceed the aforementioned OSHA Action Level.

OSHA states that until the employer performs an exposure assessment (or can supply prior data regarding the same type of work which may exempt them from the standard) and documents that employees are not exposed

above the permissible exposure limit (PEL) of greater than 50 µg/m³ of air, the employer must treat employees as if they were exposed above the PEL for the following operations:

- manual demolition of structures, manual scraping, manual sanding, and use of heat gun where lead-containing coatings or paints are present;
- abrasive blasting enclosure movement and removal;
- power tool cleaning;
- lead burning;
- using lead-containing mortar or spray painting with lead-containing paint;
- abrasive blasting, rivet busting, or welding, cutting, or burning on any structure where lead-containing coatings or paint are present;
- cleanup activities where dry expendable abrasive are used; and
- any other task the employer believes may cause exposure in excess of the PEL.

The contractor must provide respiratory protection, protective work clothing and equipment, change areas, hand washing facilities, biological monitoring, and training until an exposure assessment has determined that the work activity will result in an exposure below the PEL. Additional requirements under this standard include a written compliance program as well as record keeping.

Other Hazardous Materials

As part of the survey, Weston & Sampson performed a survey/inventory of potentially hazardous chemicals and mechanical equipment located within the survey areas that will require special handling and disposal prior to building renovation / demolition activities. The following hazardous materials were observed in the site buildings:

Material	Quantity
Fire extinguisher	10
6' Fluorescent bulb	30
4' Fluorescent bulb	120
Paint (5 Gallon)	10
Hydrophast paint (5 Gallon)	35
Adhesive (5 Gallon)	10
Varnish (2 Quarts)	10
Joint compound (2 Quarts)	10
Waste oil drum (55 Gallon)	1
Waste coolant drum (55 Gallon)	1

We appreciate the opportunity to assist you with this project. If you have any questions or require any additional information, please do not hesitate to contact us at (978) 532-1900.

Very truly yours,

WESTON & SAMPSON ENGINEERS, INC.



Craig Miner, LEED AP
Team Leader



Caleb Pettigrew
Environmental Scientist III

Attachments:

Laboratory Analytical results



EMSL Analytical, Inc.

5 Constitution Way, Unit A Woburn, MA 01801

Tel/Fax: (781) 933-8411 / (781) 933-8412

<http://www.EMSL.com> / bostonlab@emsl.com

EMSL Order: 132502701

Customer ID: WESA62

Customer PO:

Project ID:

Attention: Craig Miner

Weston & Sampson Engineers, Inc.

55 Walkers Brook Drive

Suite 100v

Reading, MA 01867

Project: Truro DPW

Phone: (978) 532-1900

Fax: (978) 977-0100

Received Date: 05/13/2025 10:15 AM

Analysis Date: 05/17/2025

Collected Date: 05/09/2025

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
01A 132502701-0001	Office Closet - Tan Carpet Mastic	Tan Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
01B 132502701-0002	Office Closet - Tan Carpet Mastic	Tan Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
02A 132502701-0003	Office Closet - White Leveling Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
02B 132502701-0004	Office Closet - White Leveling Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
02C 132502701-0005	Office Closet - White Leveling Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
03A 132502701-0006	Office Bathroom - Wall Sheetrock	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
03B 132502701-0007	Office Bathroom - Wall Sheetrock	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
04A 132502701-0008	Office Bathroom - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
04B 132502701-0009	Office Bathroom - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
05A 132502701-0010	Office Bathroom - Gray Sink Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
05B 132502701-0011	Office Bathroom - Gray Sink Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
06A 132502701-0012	Office Exterior - Building Paper	White Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
06B 132502701-0013	Office Exterior - Building Paper	White Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
07A 132502701-0014	2-Bay Garage Exterior - Tan Caulk on Door, Wood to Concrete	Tan Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
07B 132502701-0015	2-Bay Garage Exterior - Tan Caulk on Door, Wood to Concrete	Tan Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
08A 132502701-0016	2-Bay Garage Exterior - White Window Glazing	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Initial report from: 05/17/2025 15:15:49



EMSL Analytical, Inc.

5 Constitution Way, Unit A Woburn, MA 01801

Tel/Fax: (781) 933-8411 / (781) 933-8412

<http://www.EMSL.com / bostonlab@emsl.com>

EMSL Order: 132502701

Customer ID: WESA62

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
08B 132502701-0017	2-Bay Garage Exterior - White Window Glazing	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
09A 132502701-0018	2-Bay Garage Exterior - White Caulk on Door, Wood to Wood	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
09B 132502701-0019	2-Bay Garage Exterior - White Caulk on Door, Wood to Wood	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
10A 132502701-0020	2-Bay Garage Interior - White Window Glazing	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
10B 132502701-0021	2-Bay Garage Interior - White Window Glazing	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
11A 132502701-0022	Shop Exterior - White Window Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
11B 132502701-0023	Shop Exterior - White Window Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
12A 132502701-0024	Shop Office Exterior - White Door Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
12B 132502701-0025	Shop Office Exterior - White Door Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
13A 132502701-0026	Shop Office Exterior - Building Paper	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
13B 132502701-0027	Shop Office Exterior - Building Paper	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
14A 132502701-0028	Shed Exterior - Red Shingle	Red/Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
14B 132502701-0029	Shed Exterior - Red Shingle	Red/Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
15A 132502701-0030	Salt Shed Garage Exterior - Black Foundation Damproofing	Black Non-Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
15B 132502701-0031	Salt Shed Garage Exterior - Black Foundation Damproofing	Black Non-Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
16A 132502701-0032	Salt Shed Garage Interior - Black Rafter Sealant	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
16B 132502701-0033	Salt Shed Garage Interior - Black Rafter Sealant	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
17A 132502701-0034	Shed Exterior - Roof Shingle	Black Fibrous Homogeneous	5% Synthetic 5% Glass	90% Non-fibrous (Other)	None Detected

Initial report from: 05/17/2025 15:15:49



EMSL Analytical, Inc.

5 Constitution Way, Unit A Woburn, MA 01801

Tel/Fax: (781) 933-8411 / (781) 933-8412

<http://www.EMSL.com/bostonlab@emsl.com>

EMSL Order: 132502701

Customer ID: WESA62

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
17B 132502701-0035	Shed Exterior - Roof Shingle	Black Fibrous Homogeneous	5% Synthetic 5% Glass	90% Non-fibrous (Other)	None Detected
18A 132502701-0036	Concrete Shed Exterior - Gray Caulk	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
18B 132502701-0037	Concrete Shed Exterior - Gray Caulk	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
19A 132502701-0038	Concrete Shed Exterior - White Window Glazing	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
19B 132502701-0039	Concrete Shed Exterior - White Window Glazing	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
20A 132502701-0040	Concrete Shed Interior - White Caulk	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
20B 132502701-0041	Concrete Shed Interior - White Caulk	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
21A 132502701-0042	4-Bay Garage Exterior - White Window Glazing	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
21B 132502701-0043	4-Bay Garage Exterior - White Window Glazing	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
22A 132502701-0044	4-Bay Garage Exterior - Corner White Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
22B 132502701-0045	4-Bay Garage Exterior - Corner White Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
23A 132502701-0046	4-Bay Garage Exterior - White Window Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
23B 132502701-0047	4-Bay Garage Exterior - White Window Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
24A 132502701-0048	Shed - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
24B 132502701-0049	Shed - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
25A 132502701-0050	4-Bay Garage Interior - Expansion Joint	Black Non-Fibrous Homogeneous	15% Cellulose	85% Non-fibrous (Other)	None Detected
25B 132502701-0051	4-Bay Garage Interior - Expansion Joint	Black Non-Fibrous Homogeneous	15% Cellulose	85% Non-fibrous (Other)	None Detected
26A 132502701-0052	4-Bay Garage Office - Sink Undercoat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
26B 132502701-0053	4-Bay Garage Office - Sink Undercoat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Initial report from: 05/17/2025 15:15:49



EMSL Analytical, Inc.

5 Constitution Way, Unit A Woburn, MA 01801

Tel/Fax: (781) 933-8411 / (781) 933-8412

<http://www.EMSL.com> / bostonlab@emsl.com

EMSL Order: 132502701

Customer ID: WESA62

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
27A 132502701-0054	4-Bay Garage Office - Black Mastic on Wall	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
27B 132502701-0055	4-Bay Garage Office - Black Mastic on Wall	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
28A 132502701-0056	4-Bay Garage Office - Sheetrock	Gray/Tan Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
28B 132502701-0057	4-Bay Garage Office - Sheetrock	Gray/Tan Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
29A 132502701-0058	4-Bay Garage Office - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
29B 132502701-0059	4-Bay Garage Office - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
30A 132502701-0060	4-Bay Garage Bathroom - Gray Window Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
30B 132502701-0061	4-Bay Garage Bathroom - Gray Window Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
31A 132502701-0062	4-Bay Garage Boiler Room - Sheetrock	Gray/Tan Fibrous Homogeneous	10% Cellulose 2% Glass	88% Non-fibrous (Other)	None Detected
31B 132502701-0063	4-Bay Garage Boiler Room - Sheetrock	Gray/Tan Fibrous Homogeneous	10% Cellulose 2% Glass	88% Non-fibrous (Other)	None Detected
32A 132502701-0064	4-Bay Garage Boiler Room - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
32B 132502701-0065	4-Bay Garage Boiler Room - Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
33A 132502701-0066	4-Bay Garage Interior - Ceiling Panel	Brown/White Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
33B 132502701-0067	4-Bay Garage Interior - Ceiling Panel	Brown/White Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
34A 132502701-0068	4-Bay Garage Attic - Black Building Paper	Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected
34B 132502701-0069	4-Bay Garage Attic - Black Building Paper	Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected
35A 132502701-0070	4-Bay Garage Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
35B 132502701-0071	4-Bay Garage Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
36A 132502701-0072	4-Bay Garage Exterior - Roof Paper	Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected

Initial report from: 05/17/2025 15:15:49



EMSL Analytical, Inc.

5 Constitution Way, Unit A Woburn, MA 01801

Tel/Fax: (781) 933-8411 / (781) 933-8412

<http://www.EMSL.com> / bostonlab@emsl.com

EMSL Order: 132502701

Customer ID: WESA62

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
36B 132502701-0073	4-Bay Garage Exterior - Roof Paper	Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected
37A 132502701-0074	Shop Office Shed - Roof Shingle	Black Fibrous Homogeneous	10% Synthetic	90% Non-fibrous (Other)	None Detected
37B 132502701-0075	Shop Office Shed - Roof Shingle	Black Fibrous Homogeneous	10% Synthetic	90% Non-fibrous (Other)	None Detected
38A 132502701-0076	Shop/Shop Office Exterior - White Roof Trim Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
38B 132502701-0077	Shop/Shop Office Exterior - White Roof Trim Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
39A 132502701-0078	Shop Exterior - Black Caulk	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
39B 132502701-0079	Shop Exterior - Black Caulk	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
40A 132502701-0080	Shop Office Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
40B 132502701-0081	Shop Office Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
41A 132502701-0082	Shop Office Exterior - White Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
41B 132502701-0083	Shop Office Exterior - White Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
42A 132502701-0084	Shop Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
42B 132502701-0085	Shop Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
43A 132502701-0086	Shop 2-Bay Garage Exterior - Tan Seam Sealant	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
43B 132502701-0087	Shop 2-Bay Garage Exterior - Tan Seam Sealant	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
44A 132502701-0088	2-Bay Garage Interior - Ceiling Sheetrock	Gray/Tan Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
44B 132502701-0089	2-Bay Garage Interior - Ceiling Sheetrock	Gray/Tan Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
45A 132502701-0090	Office Exterior - Roof Shingle	Black Non-Fibrous Homogeneous	30% Cellulose	70% Non-fibrous (Other)	None Detected
45B 132502701-0091	Office Exterior - Roof Shingle	Black Non-Fibrous Homogeneous	30% Cellulose	70% Non-fibrous (Other)	None Detected

Initial report from: 05/17/2025 15:15:49



EMSL Analytical, Inc.

5 Constitution Way, Unit A Woburn, MA 01801

Tel/Fax: (781) 933-8411 / (781) 933-8412

<http://www.EMSL.com/bostonlab@emsl.com>

EMSL Order: 132502701

Customer ID: WESA62

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
46A 132502701-0092	Office Exterior - Roof Paper	Black Non-Fibrous Homogeneous	60% Cellulose	40% Non-fibrous (Other)	None Detected
46B 132502701-0093	Office Exterior - Roof Paper	Black Non-Fibrous Homogeneous	60% Cellulose	40% Non-fibrous (Other)	None Detected
47A 132502701-0094	Office Addition Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
47B 132502701-0095	Office Addition Exterior - Roof Shingle	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
48A 132502701-0096	Office Addition Exterior - Roof Paper	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
48B 132502701-0097	Office Addition Exterior - Roof Paper	Black Fibrous Homogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
49A 132502701-0098	TP - 7 - 4-Bay Garage Exterior - Foundation Damproofing	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
49B 132502701-0099	TP - 7 - 4-Bay Garage Exterior - Foundation Damproofing	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
50A 132502701-0100	TP - 7 - 4-Bay Garage Exterior - Addition Foundation Damproofing	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
50B 132502701-0101	TP - 7 - 4-Bay Garage Exterior - Addition Foundation Damproofing	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Analyst(s)

Kevin Pine (101)

Steve Grise, Laboratory Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. Woburn, MA NVLAP Lab Code 101147-0, CT PH-0315, MA AA000188, RI PLM00139, VT AL998919, ME LB-0039

Initial report from: 05/17/2025 15:15:49



EMSL ANALYTICAL, INC.
TESTING LABS • PRODUCTS • TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

132502701

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

PHONE: (800) 220-3675
EMAIL: CinnAslab@EMSL.com

Customer Information	Customer ID:		Billing Information	Billing ID:	
	Company Name:	Weston & Sampson		Company Name:	
	Contact Name:	Craig Miner		Billing Contact:	
	Street Address:	55 Walkers Brook Drive		Street Address:	
	City, State, Zip:	Reading, MA 01867		Country: USA	City, State, Zip:
	Phone:	1-800-SAMPSON		Phone:	
	Email(s) for Report:	minerc@wseinc.com, Pettigrew.Caleb@wseinc.com		Email(s) for Invoice:	
Project Information					
Project Name/No: Truro DPW			Purchase Order:		
EMSL LIMS Project ID: (If applicable, EMSL will provide)			US State where samples collected: MA		
			State of Connecticut (CT) must select project location: ☐ Commercial (Taxable) ☐ Residential (Non-Taxable)		
Sampled By Name: Caleb Pettigrew		Sampled By Signature: [Signature]		Date Sampled: 5-9-25	
				No. of Samples in Shipment: 101	
Turn-Around-Time (TAT)					
☐ 3 Hour ☐ 6 Hour ☐ 24 Hour ☐ 32 Hour ☐ 48 Hour ☐ 72 Hour ☐ 96 Hour ☒ 1 Week ☐ 2 Week					
Please call ahead for large projects and/or turnaround times 6 Hours or Less. *32 Hour TAT available for select tests only; samples must be submitted by 11:30am.					
PLM - Bulk (reporting limit)			Test Selection		
☒ PLM EPA 600/R-93/116 (<1%) ☐ PLM EPA NOB (<1%) ☐ POINT COUNT ☐ 400 (<0.25%) ☐ 1,000 (<0.1%) ☐ POINT COUNT w/ GRAVIMETRIC ☐ 400 (<0.25%) ☐ 1,000 (<0.1%) ☐ NIOSH 9002 (<1%) ☐ NYS 198.1 (Friable - NY) ☐ NYS 198.6 NOB (Non-Friable - NY) ☐ NYS 198.8 (Vermiculite SM-V)			TEM - Bulk ☐ TEM EPA NOB ☐ NYS NOB 198.4 (Non-Friable - NY) ☐ TEM EPA 600/R-93/116 w Milling Prep (0.1%) Other Tests (please specify) ☒ Positive Stop - Clearly Identified Homogeneous Areas (HA)		
Sample Number	HA Number	Sample Location		Material Description	
01A-B		Office Closet		Tan carpet mastic	
02A-C		↓		white leveling compound	
03A-B		Office Bathroom		wall sheetrock	
04A-B		↓		Joint compound	
05A-B		↓		Great Sinc caulk	
06A-B		Office Exterior		Building paper	
07A-B		2-Bay Garage Exterior		Tan caulk on door, wood to concrete	
08A-B		↓		white window glazing	
09A-B		↓		white caulk on door, wood to wood	
10A-B		2-Bay Garage Interior		white window glazing	
Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)					
Method of Shipment: Drop-off Relinquished by: [Signature] Date/Time: 5-13-25 10:00 Relinquished by: [Signature] Date/Time:					
Sample Condition Upon Receipt: REC'D 8M 1015 Received by: EMSL-BOSTON MAY 13 2025 Received by: [Signature] Date/Time:					

Controlled Document - Asbestos Bulk R7 9/14/2021

☒ AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



EMSL ANALYTICAL, INC.
TESTING LABS • PRODUCTS • TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

132502701

PHONE: (800) 220-3675
EMAIL: CinnAslab@EMSL.com

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

Sample Number	HA Number	Sample Location	Material Description
11A-B		Shop Exterior	White window caulk
12A-B		Shop office Exterior	White door caulk
13A-B		↓	Building paper
14A-B		Shed Exterior	Red shingle
15A-B		Salt Shed Garage Exterior	Black foundation dampproofing
16A-B		Salt Shed Garage Interior	Black rafter sealant
17A-B		Shed Exterior	Roof shingle
18A-B		Concrete shed Exterior	Green caulk
19A-B		↓	White window glazing
20A-B		Concrete shed Interior	White caulk
21A-B		4-Bay Garage Exterior	White window glazing
22A-B		↓	Corner white caulk
23A-B		↓	White window caulk
24A-B		Shed	Roof shingle
25A-B		4-Bay Garage Interior	Expansion joint
26A-B		4-Bay Garage Office	Sink undercoat
27A-B		↓	Black mesh on wall
28A-B		↓	Sheetrock
29A-B		↓	Joint compound
30A-B		4-Bay Garage Bathroom	Green window caulk
31A-B		4-Bay Garage Boiler Room	Sheetrock
32A-B		↓	Joint compound
33A-B		4-Bay Garage Interior	Ceiling panel
34A-B		4-Bay Garage Attic	Black building paper
35A-B		4-Bay Garage Exterior	Roof shingle

Method of Shipment: <i>drop-off</i>	Sample Condition Upon Receipt: <i>REC'D</i>
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>
Date/Time: <i>5-13-25 10:00</i>	Date/Time: <i>MAY 13 2025</i>
Relinquished by:	Received by: <i>EMSL-BOSTON</i>

Controlled Document - Asbestos Bulk R7 09/14/2021

☒ AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

Page 2 of 3

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

EMSL Order Number / Lab Use Only

Cinnaminson, NJ 08077

EMAIL: CinnAsblab@EMSL.com

132502701

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

Controlled Document - COC-05 Asbestos R16 10/26/2021

☒ **AGREE TO ELECTRONIC SIGNATURE** (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

**EMSL Analytical, Inc.**

3303 Parkway Center Court, Orlando, FL, 32808
Telephone: (407)-599-5887 Fax: (407)-599-9063
www.emsl.com

EMSL Order ID: 342551235
LIMS Reference ID: JD51235
EMSL Customer ID: WESA62

Attention: Craig Miner

Weston & Sampson Engineers, Inc. [WESA62]
55 Walkers Brook Drive, Suite 100v
Reading, MA 01867
(978) 532-1900
minerc@wseinc.com

Project Name: Truro DPW

Customer PO:
EMSL Sales Rep: Josh Silverman

Received: 05/14/2025 10:22
Reported: 05/21/2025 10:10

Analytical Results

Analyte	Results	RL	Weight(g)	Prep Date & Tech	Prep Method	Analysis Date & Analyst	Analytical Method	Q	DF
Client Sample ID: L1/Office Bathroom, Light Blue Wall Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-01		
Lead	<0.0081 % wt	0.0081 % wt	0.1975	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									
Client Sample ID: L2/Office Exterior, White Trim Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-02		
Lead	11.9 % wt	0.582 % wt	0.2751	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	D	100
Sample Comments:									
Client Sample ID: L3/2- Bay Garage Exterior, Grey/Green Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-03		
Lead	0.147 % wt	0.0064 % wt	0.2534	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									
Client Sample ID: L4/Shop Office Exterior, Green Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-04		
Lead	<0.0064 % wt	0.0064 % wt	0.2943	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									
Client Sample ID: L5/Salt Shed Garage Exterior, Grey Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-05		
Lead	<0.0064 % wt	0.0064 % wt	0.2561	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									
Client Sample ID: L6/4- Bay Garage Exterior, Grey Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-06		
Lead	0.0105 % wt	0.0064 % wt	0.274	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									
Client Sample ID: L7/4- Bay Garage Interior, Office White Wall							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-07		
Lead	<0.0064 % wt	0.0064 % wt	0.254	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									
Client Sample ID: L8/4- Bay Garage Interior, White Paint							Date Sampled: 05/13/25		
Matrix: Chips							LIMS Reference ID: JD51235-08		
Lead	<0.0064 % wt	0.0064 % wt	0.2587	05/15/25 DT	SW-846 3050B	05/15/25 SM	SW 846-7000B	1	
Sample Comments:									

**EMSL Analytical, Inc.**

3303 Parkway Center Court, Orlando, FL, 32808
Telephone: (407)-599-5887 Fax: (407)-599-9063
www.emsl.com

EMSL Order ID: 342551235

LIMS Reference ID: JD51235

EMSL Customer ID: WESA62

Attention: Craig Miner

Weston & Sampson Engineers, Inc. [WESA62]
55 Walkers Brook Drive, Suite 100v
Reading, MA 01867
(978) 532-1900
miner@wseinc.com

Project Name: Truro DPW**Customer PO:****EMSL Sales Rep:** Josh Silverman**Received:** 05/14/2025 10:22**Reported:** 05/21/2025 10:10**Certified Analyses included in this Report**

Analyte	Certifications
SW 846-7000B in Chips	
Lead	34-AIHA ELLAP, 34-LA, 34-OH

List of Certifications

Code	Description	Number	Expires
34-LA	LA - Asbestos (PCM, PLM and TEM), Fungi and Bacteria, Lead and Metals	0519	06/30/2027
34-AIHA ELLAP	American Industrial Hygiene Association (AIHA LAP, LLC) - ELLAP	163563	03/01/2026
34-AIHA IHLAP	American Industrial Hygiene Association (AIHA LAP, LLC) - IHLAP	163563	03/01/2026
34-A2LA Food	A2LA Food Microbiology Certificate	2845.49	03/31/2026
34-OH	OH - Lead in Paint Chips, Wipes, Soil and Air	E10057	11/22/2025

Please see the specific Field of Testing (FOT) on www.emsl.com for a complete listing of parameters for which EMSL is certified.

Notes and Definitions

Item	Definition
D	Analyte was reported from a dilution run.
(Dig)	For metals analysis, sample was digested.
[2C]	Reported from the second channel in dual column analysis.
DA	Direct Analysis
DF	Dilution Factor
MDL	Method Detection Limit.
ND	Analyte was NOT DETECTED at or above the detection limit.
NR	Spike/Surrogate showed no recovery.
Q	Qualifier
RCS	Respirable Crystalline Silica
RL	Reporting Limit
Wet	Sample is not dry weight corrected.

Measurement of uncertainty and any applicable definitions of method modifications are available upon request. Per EPA NLLAP policy, sample results are not blank corrected.

**EMSL Analytical, Inc.**

3303 Parkway Center Court, Orlando, FL, 32808
Telephone: (407)-599-5887 Fax: (407)-599-9063
www.emsl.com

EMSL Order ID: 342551235**LIMS Reference ID:** JD51235**EMSL Customer ID:** WESA62**Attention:** Craig Miner

Weston & Sampson Engineers, Inc. [WESA62]
55 Walkers Brook Drive, Suite 100v
Reading, MA 01867
(978) 532-1900
minerc@wseinc.com

Project Name: Truro DPW**Customer PO:****EMSL Sales Rep:** Josh Silverman**Received:** 05/14/2025 10:22**Reported:** 05/21/2025 10:10

Heather Ohye Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. QC sample results are within quality control criteria and met method specifications unless otherwise noted. All results for soil samples are reported on a dry weight basis, unless otherwise noted.

Analysis following EMSL SOP for the Determination of Environmental Lead by FLAA. The laboratory has a reporting limit of 0.0064% by wt., based upon a minimum sample weight of 0.25g submitted to the lab, and is not responsible for any result or reporting limit provided in mg/cm² since it is dependent upon an area value provided by non-lab personnel. A "<" (less than) result signifies that the analyte was not detected at or above the reporting limit. Measurement of uncertainty and definitions of modifications are available upon request. Results in this report are not blank corrected unless specified.



EMSL ANALYTICAL, INC.
TESTING LABS • PRODUCTS • TRAINING

T065559

Lead Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

JD51235

PHONE: (800) 220-3675

EMAIL: CinnaminsonLeadLab@emsl.com

Customer Information	Customer ID:			Billing Information	Billing ID:				
	Company Name:	Weston & Sampson			Company Name:				
	Contact Name:	Craig Miner			Billing Contact:				
	Street Address:	55 Walkers Brook Drive			Street Address:				
	City, State, Zip:	Reading, MA 01867	Country:		USA	City, State, Zip:		Country:	
	Phone:	1-800-SAMPSON			Phone:				
Email(s) for Report:				miner@wseinc.com, Pettigrew.Caleb@wseinc.com		Email(s) for Invoice:			

Project Information				
Project Name/No:	Truro DPW		Purchase Order:	
EMSL LIMS Project ID:	(If applicable, EMSL will provide)		US State where samples collected:	MA
Sampled By Name:		Caleb Pettigrew	State of Connecticut (CT) must select project location:	☐ Commercial (Taxable) ☐ Residential (Non-Taxable)
Sampled By Signature:		Caleb Pettigrew	No. of Samples in Shipment:	8

Turn-Around-Time (TAT)									
☐ 3 Hour	☐ 6 Hour	☐ 24 Hour	☐ 32 Hour	☐ 48 Hour	☐ 72 Hour	☐ 96 Hour	☒ 1 Week	☐ 2 Week	
Please call ahead for large projects and/or turnaround times 6 Hours or Less. *32 Hour TAT available for select tests only; samples must be submitted by 11:30am.									

MATRIX	METHOD	INSTRUMENT	REPORTING LIMIT	SELECTION
CHIPS ☒ % by wt. ☐ ppm (mg/kg) ☐ mg/cm ²	SW 846-7000B	Flame Atomic Absorption	0.008% (80ppm)	☒
Reporting Limit based on a minimum 0.25g sample weight.	SW 846-6010D	ICP-OES	0.0004% (4ppm)	☐
**Not appropriate for Ceramic Tiles - XRF is recommended	NIOSH 7082	Flame Atomic Absorption	4µg/filter	☐
AIR	NIOSH 7300M / NIOSH 7303M	ICP-OES	0.5µg/filter	☐
	NIOSH 7300M / NIOSH 7303M	ICP-MS	0.05µg/filter	☐
WIPE ☐ ASTM ☐ NON-ASTM	SW 846-7000B	Flame Atomic Absorption	10µg/wipe	☐
If no box is checked, non-ASTM Wipe is assumed	SW 846-6010D	ICP-OES	1.0µg/wipe	☐
TCLP	SW 846-1311 / 7000B / SM 3111B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	SW 846-1311 / SW 846-6010D*	ICP-OES	0.1 mg/L (ppm)	☐
SPLP	SW 846-1312 / 7000B / SM 3111B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	SW 846-1312 / SW 846-6010D*	ICP-OES	0.1 mg/L (ppm)	☐
TTLC	22 CCR App. II, 7000B	Flame Atomic Absorption	40mg/kg (ppm)	☐
	22 CCR App. II, SW 846-6010D*	ICP-OES	2mg/kg (ppm)	☐
STLC	22 CCR App. II, 7000B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	22 CCR App. II, SW 846-6010D*	ICP-OES	0.1 mg/L (ppm)	☐
Soil	SW 846-7000B	Flame Atomic Absorption	40mg/kg (ppm)	☐
	SW 846-6010D*	ICP-OES	2mg/kg (ppm)	☐
Wastewater	SM 3111B / SW 846-7000B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
Unpreserved ☐	EPA 200.7	ICP-OES	0.020 mg/L (ppm)	☐
Preserved with HNO ₃ ☐ PH<2	EPA 200.5	ICP-OES	0.003 mg/L (ppm)	☐
Drinking Water	EPA 200.8	ICP-MS	0.001 mg/L (ppm)	☐
Unpreserved ☐	40 CFR Part 50	ICP-OES	12 µg/filter	☐
Preserved with HNO ₃ ☐ PH<2				☐
TSP/SPM Filter				☐
Other:				☐

Sample Number	Sample Location	Volume / Area	Date / Time Sampled
L1	Office Bathroom	Light blue wall paint	
L2	Office Exterior	White trim paint	
L3	2-Bay Garage Exterior	Grey/green paint	
L4	Shop Office Exterior	Green paint	
L5	Salt Shed Garage Exterior	Grey paint	

Method of Shipment: Drop-off		Sample Condition Upon Receipt:	
Relinquished by: [Signature]	Date/Time: 5-13-25 10:00	Received by: [Signature]	Date/Time: MAY 14 2025
Relinquished by: [Signature]	Date/Time:	Received by:	Date/Time:

REC'D
EMSL-BOSTON
MAY 13 2025

*6010C Available Upon Request

☒ AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



Lab Use Only

EMAIL: CinnaminsonLeadLab@emsl.com

JD51235

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

Method of Shipment: <i>Drop off</i>		Sample Condition Upon Receipt:	
Relinquished by: <i>[Signature]</i>	Date/Time: <i>5-13-25 10:00</i>	Received by: <i>[Signature]</i>	Date/Time: <i>MAY 14 2025</i>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - COC-25 Lead R17 05/09/2022

☒ **AGREE TO ELECTRONIC SIGNATURE** (By checking, I consent to signing this Chain of Custody document by electronic signature.)

REC'D EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



EMSL ANALYTICAL, INC.
TESTING LABS • PRODUCTS • TRAINING

Lead Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

PHONE: (800) 220-3675

EMAIL: CinnaminsonLeadLab@emsl.com

JD51235

Customer Information	Customer ID:			Billing Information	Billing ID:				
	Company Name:	Weston & Sampson			Company Name:				
	Contact Name:	Craig Miner			Billing Contact:				
	Street Address:	55 Walkers Brook Drive			Street Address:				
	City, State, Zip:	Reading, MA 01867	Country:		USA	City, State, Zip:		Country:	
	Phone:	1-800-SAMPSON			Phone:				
Email(s) for Report:				miner@wseinc.com, Pettigrew.Caleb@wseinc.com		Email(s) for Invoice:			

Project Information			
Project Name/No:		Truro DPW	
EMSL LIMS Project ID:		(If applicable, EMSL will provide)	
US State where samples collected:		MA	
State of Connecticut (CT) must select project location:		☐ Commercial (Taxable) ☐ Residential (Non-Taxable)	
Sampled By Name:		Caleb Pettigrew	
Sampled By Signature:		Caleb Pettigrew	
No. of Samples in Shipment		8	

Turn-Around-Time (TAT)								
☐ 3 Hour	☐ 6 Hour	☐ 24 Hour	☐ 32 Hour	☐ 48 Hour	☐ 72 Hour	☐ 96 Hour	☒ 1 Week	☐ 2 Week
Please call ahead for large projects and/or turnaround times 6 Hours or Less. *32 Hour TAT available for select tests only; samples must be submitted by 11:30am.								

MATRIX	METHOD	INSTRUMENT	REPORTING LIMIT	SELECTION
CHIPS ☒ % by wt. ☐ ppm (mg/kg) ☐ mg/cm ²	SW 846-7000B	Flame Atomic Absorption	0.008% (80ppm)	☒
Reporting Limit based on a minimum 0.25g sample weight.	SW 846-6010D	ICP-OES	0.0004% (4ppm)	☐
**Not appropriate for Ceramic Tiles - XRF is recommended	NIOSH 7082	Flame Atomic Absorption	4µg/filter	☐
AIR	NIOSH 7300M / NIOSH 7303M	ICP-OES	0.5µg/filter	☐
	NIOSH 7300M / NIOSH 7303M	ICP-MS	0.05µg/filter	☐
WIPE ☐ ASTM ☐ NON-ASTM	SW 846-7000B	Flame Atomic Absorption	10µg/wipe	☐
If no box is checked, non-ASTM Wipe is assumed	SW 846-6010D	ICP-OES	1.0µg/wipe	☐
TCLP	SW 846-1311 / 7000B / SM 3111B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	SW 846-1311 / SW 846-6010D*	ICP-OES	0.1 mg/L (ppm)	☐
SPLP	SW 846-1312 / 7000B / SM 3111B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	SW 846-1312 / SW 846-6010D*	ICP-OES	0.1 mg/L (ppm)	☐
TTLIC	22 CCR App. II, 7000B	Flame Atomic Absorption	40mg/kg (ppm)	☐
	22 CCR App. II, SW 846-6010D*	ICP-OES	2mg/kg (ppm)	☐
STLC	22 CCR App. II, 7000B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
	22 CCR App. II, SW 846-6010D*	ICP-OES	0.1 mg/L (ppm)	☐
Soil	SW 846-7000B	Flame Atomic Absorption	40mg/kg (ppm)	☐
	SW 846-6010D*	ICP-OES	2mg/kg (ppm)	☐
Wastewater	SM 3111B / SW 846-7000B	Flame Atomic Absorption	0.4 mg/L (ppm)	☐
Unpreserved ☐	EPA 200.7	ICP-OES	0.020 mg/L (ppm)	☐
Preserved with HNO ₃ ☐ PH<2	EPA 200.5	ICP-OES	0.003 mg/L (ppm)	☐
Drinking Water	EPA 200.8	ICP-MS	0.001 mg/L (ppm)	☐
Unpreserved ☐	40 CFR Part 50	ICP-OES	12 µg/filter	☐
Preserved with HNO ₃ ☐ PH<2				☐
TSP/SPM Filter				☐
Other:				☐

Sample Number	Sample Location	Volume / Area	Date / Time Sampled
L1	Office Bathroom	Light blue wall paint	
L2	Office Exterior	White trim paint	
L3	2-Bay Garage Exterior	Grey/green paint	
L4	Shop Office Exterior	Green paint	
L5	Salt Shed Garage Exterior	Grey paint	

Method of Shipment:		Sample Condition Upon Receipt:	
Relinquished by:	Date/Time:	Received by:	Date/Time:
Relinquished by:	Date/Time:	Received by:	Date/Time:

REC'D
EMSL-BOSTON
MAY 13 2025

*6010C Available Upon Request

☒ AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

Lead Chain of Custody

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

PHONE: (800) 220-3675

EMAIL: CinnaminsonLeadLab@emsl.com

JD51235

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

[illegible]

Method of Shipment:

Drop off

Sample Condition Upon Receipt:	
--------------------------------	--

Relinquished by:

Cell M

Date/Time:

Date/Time: 5-13-25 10:00

Received by:

Received by:

Received by:

Date/Time	
-----------	--

Date/Time MAY 14 2025

Relinquished by:

Date/Time:

Received by:

Date/Time

Controlled Document - COC-25 Lead R17 05/09/2022



AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

REC'D EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

TABLE OF CONTENTS

VOLUME 1 (Divisions 00 through 01)

DIVISION 00 — PROCUREMENT AND CONTRACTING REQUIREMENTS

Document 00 01 10	Table of Contents
Document 00 02 00	List of Prequalified Contractors
Document 00 11 13	Advertisement for Bids
Document 00 21 13	Instructions to Bidders
Document 00 31 32	Subsurface Data
Document 00 31 43	Permits
Document 00 41 13	Form for General Bid
Document 00 41 13.13	Form for Sub-Bid
Document 00 43 43	Prevailing Wage Rates
Document 00 45 13	General Contractor DCAM Update Statement
Document 00 45 13.13	Sub-Bid DCAM Update Statement
Document 00 52 00	Agreement
Document 00 52 00.13	Subcontract Form
Document 00 61 13.13	Performance Bond
Document 00 61 13.16	Payment Bond
Document 00 63 25	Substitution Request Form
Document 00 63 63	State Regs-ATT. D-Change Order
Document 00 72 00	General Conditions (EJDOC 2018)
Document 00 73 00	Supplementary Conditions (EJDOC 2018)
Document 00 73 73.13	State Statutes and Regulations – Commonwealth of Massachusetts – Revisions to General Conditions
Document 00 73 73.43	Attachment B - Excerpts from MGL Chapters 30, 82, and 149

DIVISION 01 – GENERAL REQUIREMENTS

Section 01 03 00	Alternates
Section 01 11 00	Control of Work and Materials
Section 01 12 16	Scope and Sequence of Work
Section 01 14 00	Special Provisions
Section 01 14 19.16	Dust Control
Section 01 22 00	Measurement and Payment
Section 01 25 13	Product Substitution Procedures
Section 01 31 00	Project Management and Coordination
Section 01 31 19.23	Construction Meetings
Section 01 32 16	Construction Scheduling
Section 01 32 33	Construction Photographs
Section 01 33 23	Submittals
Section 01 33 23.13	Submittal of Operation and Maintenance Manuals
Section 01 35 29	Health and Safety Plan
Section 01 42 00	References
Section 01 43 39	Mock-Ups

Section 01 45 00	Quality Control
Section 01 45 23	Structural Tests and Inspections
Section 01 45 29	Testing Laboratory Services
Section 01 52 13	Temporary Facilities
Section 01 55 26.13	Signage (Traffic Control)
Section 01 56 00	Construction Zone Safety Plan
Section 01 57 19	Environmental Protection
Section 01 73 29	Cutting, Coring, and Patching
Section 01 74 13	Cleaning Up
Section 01 78 00	Project Closeout
Section 01 78 39	Project As-Built Record Drawings
Section 01 91 13	General Commissioning Requirements
Section 01 91 13.01	Commissioning of Building Assemblies
Section 01 92 13	Operations and Maintenance Manuals

VOLUME 2

(Divisions 02 through 22)

DIVISION 02 – EXISTING CONDITIONS

Section 02 41 13.36	Utility Abandonment
Section 02 41 16	Demolition
Section 02 61 00.16	Handling, Transportation, Reuse and Off-Site Disposal of Excavated Material
Section 02 61 26.13	Asbestos Abatement for Underground Utilities
Section 02 80 00.13	Universal and Hazardous Waste
Section 02 82 33	Asbestos Abatement
Section 02 83 19	Lead Based Coatings Removal
Section 02 83 90	Abatement of PCB-Containing Materials

DIVISION 03 - CONCRETE

Section 03 05 00	Field Concrete
Section 03 05 10	Concrete Moisture Vapor Reduction Admixture
Section 03 05 13	Concrete Sealers
Section 03 30 00	Cast-in-Place Concrete
Section 03 48 46	Precast Concrete Block

DIVISION 04 — MASONRY

Section 04 00 01*	Masonry Filed Sub-Bid Requirements * Filed Sub-Bid Required
Section 04 20 00 *	Unit Masonry (* Filed Sub-Bid Required as part of 04 00 01)
Section 04 72 00 *	Cast Stone Masonry (* Filed Sub-Bid Required as part of 04 00 01)

DIVISION 05 — METALS

Section 05 00 01 *	Miscellaneous and Ornamental Iron Filed Sub-Bid Requirements * Filed Sub-Bid Required
Section 05 40 00	Cold-Formed Metal Framing
Section 05 50 00 *	Metal Fabrications (*Filed Sub-Bid Required as part of 05 00 01)
Section 05 50 01 *	Miscellaneous Metals – Salt Shed (*Filed Sub-Bid Required as part of 05 00 01)
Section 05 51 13 *	Metal Pan Stairs (*Filed Sub-Bid Required as part of 05 00 01)
Section 05 51 19 *	Metal Grating Stairs (*Filed Sub-Bid Required as part of 05 00 01)
Section 05 52 13 *	Pipe and Tube Railings (*Filed Sub-Bid Required as part of 05 00 01)

DIVISION 06 — WOOD, PLASTICS AND COMPOSITES

Section 06 10 00	Rough Carpentry
Section 06 16 00	Sheathing
Section 06 20 13	Exterior Finish Carpentry
Section 06 20 23	Interior Finish Carpentry
Section 06 40 23	Interior Architectural Woodwork
Section 06 64 00	Plastic Paneling

DIVISION 07 — THERMAL AND MOISTURE PROTECTION

Section 07 00 01*	Waterproofing, Dampproofing, and Caulking Requirements *Filed Sub-Bid Required
Section 07 00 02*	Roofing and Flashing *Filed Sub-Bid Required
Section 07 11 13*	Bituminous Dampproofing (*Filed Sub-Bid Required as part of 07 00 01)
Section 07 13 53*	Membrane Water Proofing (*Filed Sub-Bid Required as part of 07 00 01)
Section 07 21 00	Thermal Insulation
Section 07 21 19	Formed-In-Place Insulation
Section 07 26 00	Vapor Retarders
Section 07 27 13*	Modified Bituminous Sheet Air Barriers (*Filed Sub-Bid Required as part of 07 00 01)
Section 07 27 26	Fluid-Applied Membrane Air Barriers
Section 07 42 93	Soffit Panels
Section 07 54 19 *	Polyvinyl Chloride (PVC) Roofing (*Filed Sub-Bid Required as part of 07 00 02)
Section 07 62 00 *	Sheet Metal Flashing and Trim (*Filed Sub-Bid Required as part of 07 00 02)
Section 07 84 43	Joint Firestopping
Section 07 92 00 *	Joint Sealants (*Filed Sub-Bid Required as part of 07 00 01)

DIVISION 08 — OPENINGS

Section 08 11 00	Metal Doors and Frames
Section 08 11 19	Stainless-Steel Doors and Frames
Section 08 14 16	Flush Wood Doors
Section 08 17 43	Integrated Composite Door Opening Assemblies
Section 08 31 13	Access Doors and Frames
Section 08 36 13	Sectional Doors
Section 08 43 13	Aluminum Framed Storefronts
Section 08 45 13	Structured-Polycarbonate-Panel Assemblies
Section 08 71 00	Door Hardware
Section 08 80 00 *	Glazing * *Filed Sub-Bid Required
Section 08 91 19	Fixed Louvers

DIVISION 09 — FINISHES

Section 09 00 01 *	Resilient Floors Filed Sub-Bid Requirements * Filed Sub-Bid Required
Section 09 05 06	Common Work Results for Flooring
Section 09 21 16.23	Gypsum Board Shaft Wall Assemblies
Section 09 22 16	Non-Structural Metal Framing
Section 09 29 00	Gypsum Board
Section 09 30 13*	Ceramic Tiling* *Filed Sub-Bid Required
Section 09 51 23*	Acoustical Tile Ceilings* *Filed Sub-Bid Required
Section 09 65 13 *	Resilient Base and Accessories (*Filed Sub-Bid Required as part of 09 00 01)
Section 09 65 19 *	Resilient Tile Flooring (*Filed Sub-Bid Required as part of 09 00 01)
Section 09 65 66 *	Resilient Athletic Flooring (*Filed Sub-Bid Required as part of 09 00 01)
Section 09 67 23	Resinous Flooring
Section 09 68 13	Tile Carpeting
Section 09 77 23	Plastic Wall Panels
Section 09 90 00*	Painting* (*Filed Sub-Bid Required as part of 09 90 00)

DIVISION 10 — SPECIALTIES

Section 10 14 16	Plaques
Section 10 14 19	Dimensional Letter Signage
Section 10 14 20	Building Signage
Section 10 14 23.16	Room-Identification Panel Signage
Section 10 21 13.19	Plastic Toilet Compartments
Section 10 22 13	Wire Mesh Partitions
Section 10 26 00	Wall & Door Protection
Section 10 28 00	Toilet, Bath, and Laundry Accessories
Section 10 44 13	Fire Extinguisher Cabinets

Section 10 44 16	Fire Extinguishers
Section 10 51 13	Metal Lockers
Section 10 75 16	Ground-Set Flagpoles

DIVISION 11 — EQUIPMENT

Section 11 11 26	Vehicle Washing Equipment
Section 11 11 29	Lubrication Dispensing System
Section 11 24 23	Fall Protection
Section 11 30 13	Residential Appliances

DIVISION 12 — FURNISHINGS

Section 12 24 13	Roller Window Shades
Section 12 35 30	Residential Casework
Section 12 36 61.16	Solid Surfacing Countertops
Section 12 40 00	Equipment, Furnishings and Accessories
Section 12 48 13	Entrance Floor Mats
Section 12 48 16	Entrance Floor Grilles

DIVISION 13 — SPECIAL CONSTRUCTION

Section 13 42 00	Pre-Engineered Metal Building
-------------------------	--------------------------------------

DIVISION 14 — CONVEYING SYSTEMS

Section 14 22 13	Crane Systems
Section 14 45 00	Vehicle Lifts

DIVISION 21 — FIRE SUPPRESSION

Section 21 00 01 *	Fire Suppression Filed Sub-Bid Requirements *Filed Sub-Bid Required
Section 21 00 50 *	Basic Fire Suppression Requirements (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 05 23 *	General-Duty Valves for Fire Protection Piping (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 05 29 *	Hangers and Supports for Fire Suppression Piping and Equipment (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 05 48 *	Vibration and Seismic Controls for Fire Suppression Piping (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 11 00 *	Facility Fire-Suppression Water-Service Piping (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 11 19 *	Fire Department Connections (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 13 13 *	Wet-Pipe Sprinkler Systems (* Filed Sub-Bid Required as part of Section 21 00 01)
Section 21 13 16 *	Dry-Pipe Sprinkler Systems (* Filed Sub-Bid Required as part of Section 21 00 01)

DIVISION 22 — PLUMBING

Section 22 00 01 *	Plumbing Filed Sub-Bid Requirements *Filed Sub-Bid Required
Section 22 00 50 *	Basic Plumbing Requirements (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 05 13 *	Common Motor Requirements for Plumbing Equipment (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 05 19 *	Meters and Gages for Plumbing Piping (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 05 23 *	Valves for Plumbing Piping (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 05 29 *	Hangers and Supports for Plumbing Piping and Equipment (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 05 48 *	Vibration and Seismic Controls for Plumbing Piping and Equipment (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 07 19 *	Plumbing Piping Insulation (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 08 00 *	Commissioning of Plumbing (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 11 16 *	Domestic Water Piping (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 11 19 *	Domestic Water Piping Specialties (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 11 22 *	Domestic Water Pumps (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 13 16 *	Sanitary Waste and Vent Piping (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 13 19 *	Sanitary Waste Piping Specialties (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 13 20 *	Sanitary Drains (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 13 23 *	Sanitary Waste Interceptors (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 14 13 *	Facility Storm Drainage Piping (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 14 23 *	Storm Drain Piping Specialties (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 15 13 *	General-Service Compressed-Air Piping (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 15 19 *	General-Service Packaged Air Compressors and Receivers (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 34 00 *	Fuel-Fired Domestic Water Heater (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 42 00 *	Commercial Plumbing Fixtures (* Filed Sub-Bid Required as part of Section 22 00 01)
Section 22 45 00 *	Emergency Plumbing Fixtures (* Filed Sub-Bid Required as part of Section 22 00 01)

VOLUME 3
(Divisions 23 through 33)

DIVISION 23 — HEATING, VENTILATING AND AIR CONDITIONING

Section 23 00 01 *	HVAC Filed Sub-Bid Requirements *Filed Sub-Bid Required
Section 23 00 50 *	Basic HVAC Requirements (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 13 *	Common Motor Requirements for HVAC Equipment (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 16 *	Expansion Fittings and Loops for HVAC Piping (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 17 *	Sleeves and Sleeve Seals for HVAC Piping (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 19 *	Meters and Gages for HVAC Piping (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 23 *	General-Duty Valves for HVAC Piping (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 29 *	Hangers and Supports for HVAC Piping and Equipment (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 48 *	Vibration and Seismic Controls for HVAC (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 53 *	Identification for HVAC Piping and Equipment (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 05 93 *	Testing, Adjusting, and Balancing for HVAC (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 07 13 *	Duct Insulation (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 07 19 *	HVAC Piping Insulation (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 08 00 *	Commissioning of HVAC (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 09 00 *	Building Management System (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 09 24 *	Gas Monitoring Systems (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 21 13 *	Hydronic Piping (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 21 16 *	Hydronic Piping Specialties (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 21 23 *	Hydronic Pumps (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 23 00 *	Refrigerant Piping (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 25 13 *	Water Treatment for Closed-Loop Hydronic Systems

	(* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 31 10 *	Ductwork and Accessories (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 34 23 *	HVAC Power Ventilators (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 35 16 *	Vehicle Exhaust Systems (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 37 13 *	Air Diffusers, Registers, and Grilles (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 37 23 *	HVAC Gravity Ventilators (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 38 13	Commercial-Kitchen Hoods
Section 23 51 23 *	Gas Vents (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 57 33	Geothermal Energy – Direct Use (Heating Applications)
Section 23 72 00 *	Air to Air Energy Recovery Equipment (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 74 33 *	Dedicated Outdoor-Air Units (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 81 26 *	Split System Air-Conditioners (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 82 16 *	Heating and Cooling Coils (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 82 39 *	Unit Heaters (* Filed Sub-Bid Required as part of Section 23 00 01)
Section 23 83 16 *	Radiant Heating Hydronic Piping (* Filed Sub-Bid Required as part of Section 23 00 01)

DIVISION 26 — ELECTRICAL

Section 26 00 01 *	Electrical Filed Sub-Bid Requirements *Filed Sub-Bid Required
Section 26 00 50 *	Electrical Work – General Provisions (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 00 51 *	Electrical Temporary Light and Power (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 19 *	Low Voltage Electrical Power Conductors and Cables (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 26 *	Grounding and Bonding for Electrical Systems (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 29 *	Hangers and Supports for Electrical Systems (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 33 *	Raceways and Boxes for Electrical Systems (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 44 *	Sleeves and Seals for Electrical Raceways and Cabling (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 48 *	Seismic Controls for Electrical Work (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 53 *	Identification for Electrical Systems

	(* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 05 73 *	Protective Device Coordination (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 08 00 *	Commissioning of Electrical Systems (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 09 23 *	Lighting Control Devices (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 09 43 *	Lighting Control System (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 09 43.23 *	Relay-Based Lighting Controls (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 22 13 *	Low-Voltage Distribution Transformers (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 24 16 *	Panelboards (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 27 13 *	Electricity Metering (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 27 26 *	Wiring Devices (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 28 16 *	Enclosed Switches and Circuit Breakers (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 29 13 *	Manual and Magnetic Motor Controllers (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 29 23 *	Variable Frequency Motor Controllers (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 31 00	Photovoltaic Collectors
Section 26 32 13.14 *	Diesel Engine Generator
Section 26 36 00 *	Transfer Switches (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 43 13 *	Surge Protection for Low-Voltage Electrical Power Circuits (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 51 00 *	Interior Lighting (* Filed Sub-Bid Required as part of Section 26 00 01)
Section 26 56 00 *	Exterior Lighting (* Filed Sub-Bid Required as part of Section 26 00 01)

DIVISION 27 — COMMUNICATIONS

Section 27 15 13 *	Communications Copper Horizontal Cabling (* Filed Sub-Bid Required as part of Section 26 00 01)
---------------------------	---

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

Section 28 31 11 *	Digital, Addressable Fire-Alarm System (* Filed Sub-Bid Required as part of Section 26 00 01)
--------------------	--

DIVISION 31 — EARTHWORK

Section 31 00 00	Earthwork
Section 31 05 13.22	Controlled Density Fill
Section 31 05 19	Geotextile Fabric

Section 31 11 00	Clearing and Grubbing
Section 31 23 16.26	Rock Excavation and Disposal
Section 31 23 19	Dewatering
Section 31 25 00	Erosion and Sedimentation Control
Section 31 37 00	Riprap
Section 31 50 00	Support of Excavation




DIVISION 32 — EXTERIOR IMPROVEMENTS




Section 32 11 00	Sidewalk Construction and Replacement
Section 32 12 00	Paving
Section 32 14 13	Precast Concrete Unit Paving
Section 32 16 00	Curbing
Section 32 31 11	Barrier Arm Gate and Gate Operators
Section 32. 32 23.13	Segmental Retaining Wall System
Section 32 91 19	Loaming & Seeding
Section 32 93 00	Trees, Shrubs, Groundcovers and Landscaping



DIVISION 33 — UTILITIES

Section 33 05 26.13	Tracer Tape
Section 33 11 13	Water Service Connections
Section 33 11 13.13	Ductile Iron Pipe and Fittings for Water Mains
Section 33 11 13.28	HDPE Pipe
Section 33 11 13.34	Connections to Existing Water Mains
Section 33 11 13.43	Insulation for Pipelines
Section 33 12 22	Hydrants and Valves for Potable Water Work
Section 33 16 56	Ground-Level Plastic Water Storage Cisterns
Section 33 31 13.16	Polyvinyl Chloride Gravity Pipe and Fittings
Section 33 31 13.46	Connections to Existing Structures
Section 33 32 16.25	Grinder Pump Units
Section 33 34 00	On-Site Wastewater Disposal
Section 33 39 13	Precast Manholes and Catch Basins
Section 33 41 13	Reinforced Concrete Pipe
Section 33 41 13.16	Polyethylene Drainage Pipe (Perforated)
Section 33 41 13.22	Corrugated Polyethylene (HDPE) Drainage Pipe
Section 33 44 20	Downspout Boots
Section 33 44 26	Underground Stormwater Chamber System

--- END OF TABLE ---







17 TOWN HALL ROAD
TRURO, MA 02666

Weston & SampsonSM

Weston & Sampson Engineers, Inc.
100 Foxborough Boulevard, Suite 250
Foxborough, MA 02035
978.532.1900 800.SAMPS

www.westonandsampson.com

Consultant

[illegible]

COM

Sea

Issued For

SCHEMATIC DESIGN
NOT RELEASED FOR
CONSTRUCTION

Scale: AS NOTED

Date: 05/30/2025

Discussion Re

1

11

W&S Project No.: ENG24 - 155




W&S File

Drawing Title

TRUCK TURNING
PLAN
WB-40
SALT SHED

Sheet Num

FIG.3



Consultants:

[illegible][illegible]COA:

1

Seat:

Issued For:

**SCHEMATIC DESIGN
NOT RELEASED FOR
CONSTRUCTION**

Scale: AS NOTED

1

Date: 05/30/2025

Drawn By:

Reviewed By:

Approved By:




W&S Project No.: ENG24 - 1552
W&S File No.:

Drawing Title:

TRUCK TURNING
PLAN
WB-40
WASH BAY

Sheet Number:

FIG.4



Consultants:

[illegible]

COA

Seat

Issued For:

**SCHEMATIC DESIGN
NOT RELEASED FOR
CONSTRUCTION**

Scale: AS NOTED

Date:	05 /30/ 2025
Drawn By:	
Reviewed By:	
Approved By:	
W&S Project No.:	ENG24 - 1552
W&S File No.:	

Drawing Title:

TRUCK TURNING
PLAN (SU-30)
THROUGH INTERIOR
FLEET
MAINTENANCE

Sheet Number

FIG.5